

ENRON

OIL & GAS COMPANY

P.O. BOX 1815, VERNAL, UTAH 84078 (801)789-0790

September 14, 1992

Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078


RE: NOTICE OF STAKING
CHAPITA WELLS UNIT 350-14N
Sec. 14, T9S, R22E
Uintah County, Utah
Lease No. U-0282

Dear Mr. Forsman:

Attached is a Notice of Staking on the subject well.

If you require further information, please contact this office.

Very truly yours,
ENRON OIL & GAS COMPANY



George McBride
Sr. Production Foreman

Attachment

cc: Division of Oil Gas & Mining
Doug Weaver/Toni Miller
Curt Parsons
File

/lw
NOSLTR

RECEIVED

SEP 17 1992

DIVISION OF
OIL GAS & MINING

NOTICE OF STAKING

(Not to be used in place of
Application to Drill Form 9-331-C)

RMOGA
5/5/82

1. Oil Well Gas Well ☒ Other

2. Name of Operator
Enron Oil & Gas Company

3. Address of Operator or Agent
P. O. Box 1815, Vernal, Utah 84078

4. Surface Location of Well
(Governmental 1/4 or 1/4 1/4)
SW/SE 660' FSL, 1980' FEL

Attach: Topographical or other acceptable map
Showing location, access road, and lease boundaries

14. Formation Objective(s) 15. Estimated Well Depth
Wasatch 7300'

5. Lease Number
U-0282

6. If Indian, Allottee or Tribe Name
Federal Surface

7. Unit Agreement Name
Chapita Wells Unit

8. Farm or Lease Name
Chapita Wells Unit

9. Well No.
350-14N

10. Field or Wildcat Name
CWU/Wasatch

11. Sec., T., R., M., or
Blk and Survey or Area
Sec. 14, T9S, R22E

12. County or Parish 13. State
Uintah Utah

16. To Be Completed by Operator Prior to Onsite
a. Location must staked - Completed
b. Access Road Flagged - Completed
c. Sketch and/or map of location, showing road, pad dimensions, reserve pit, cuts, and fills
(To be provided at onsite)


17. To Be Considered By Operators Prior to Onsite
a. H2S Potential - NA
b. Private Surface Ownership - NA
c. Cultural Resources (Archaeology) - Completed
d. Federal Right of Way

18. Additional Information

19. Signed Linda L. Wall Title Sr. Admin. Clerk

Date 9/14/92

RECEIVED
SEP 17 1992
DIVISION OF
OIL GAS & MINING



ENRON

OIL & GAS COMPANY

P.O. BOX 1815, VERNAL, UTAH 84078 (801)789-0790

September 17, 1992

RECEIVED

SEP 24 1992

**DIVISION OF
OIL GAS & MINING**

Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

RE: APPLICATION FOR PERMIT TO DRILL
CHAPITA WELLS UNIT 350-14N
SECTION 14, T9S, R22E
UINTAH COUNTY, UTAH
LEASE NO. U-0282


Dear Mr. Forsman:

Enclosed are the original and two (2) copies of the Application for Permit to Drill and associated attachments for the referenced well.

If further information is required regarding this matter, please contact this office.

Sincerely,

ENRON OIL & GAS COMPANY



George R. McBride
Sr. Production Foreman

Attachments

cc: State Division of Oil, Gas & Mining
D. Weaver/T. Miller
Suzanne Saldivar
File

/lw
CWU350-14NAPD

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

2. TYPE OF WELL

ON
WELL ☐

CAR
WELL ☒

OTHER

SINGLE
BONE ☐

MULTIPLE
BONE ☐

3. NAME OF OPERATOR

Enron Oil & Gas Company

4. ADDRESS OF OPERATOR

P.O. Box 1815, Vernal, Utah 84078

5. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At surface

660' FSL & 1980' FEL SW/SE

6. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE

17.9 Miles Southeast of Ouray, Utah

7. DISTANCE FROM PROPOSED

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drg. unit line, if any)

3300'

8. NO. OF ACRES IN LEASE

2440

9. NO. OF ACRES ASSIGNED
TO THIS WELL

80

10. DISTANCE FROM PROPOSED LOCATION
TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1310'

11. PROPOSED DEPTH

7300'

12. ROTARY OR CABLE TOOLS

Rotary

13. ELEVATIONS (Show whether DF, RT, GR, etc.)

4923' Graded Ground

14. APPROX. DATE WORK WILL START

October 1992

23. PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | SIZE OF CASING | WEIGHT PER FOOT | SETTING DEPTH | QUANTITY OF CEMENT |
|--------------|----------------|-----------------|---------------|---|
| 12 1/4" | 9 5/8" | 32.3# | 240' | 125 sx Class "G" + 2% CaCl ₂ |
| 7 7/8" | 4 1/2" | 10.5# | 7300' | + 1/2 #/sx celloflake. 50/50 |
| | | | | Pozmix + 2% gel + 10% salt |
| | | | | to 400' above all zones of |
| | | | | interest (+ 10% excess). |
| | | | | Light cement (11 PPG+) |
| | | | | + LCM to 200' above oil |
| | | | | shale or fresh water |
| | | | | intervals (+ 5% excess). |

SEE ATTACHMENTS FOR:

8 Point Plan
Drilling Program
BOP Schematic
Surface Use and Operating Plan
Location Plat
Location Layout
Topographic Maps "A", "B", and "C"
Gas Sales Pipeline Exhibit "A"

RECEIVED

SEP 24 1992

DIVISION OF
OIL GAS & MINING

Enron Oil & Gas Company will be the
designated operator of the subject well
under Nation Wide Bond #81307603.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Linda L. Ware

TITLE

Sr. Admin. Clerk

DATE

9/17/92

(This space for Federal or State office use)

PERMIT NO.

43-047-30375

APPROVAL DATE

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL GAS AND MINING

APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

DATE

BY

WELL SPACING

649-2-3

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

T9S, R22E, S.L.B.&M.

N89°58'W - 80.32 (G.L.O.)

N0°03'E - 40.19 (G.L.O.)

N0°01'W - 40.12 (G.L.O.)

N0°31'E - 40.04 (G.L.O.)

N0°02'W - G.L.O. (Basis of Bearings)
2643.30' - (Measured)

14

CWU #350-14

Elev. Ungraded Ground - 4924'

1980'

660'

N89°48'W - 39.99 (G.L.O.)

N89°33'13"E - 2640.17' (Meas.)

LEGEND:

└─┘ = 90° SYMBOL

● = PROPOSED WELL HEAD.


▲ = SECTION CORNERS LOCATED.

ENRON OIL & GAS CO.

Well location, CWU #350-14, located as shown in the SW 1/4 SE 1/4 of Section 14, T9S, R22E, S.L.B.&M. Uintah County, Utah.

BASIS OF ELEVATION

BENCH MARK 61 EAM (1965) IN THE NE 1/4 OF SECTION 23, T9S, R22E, S.L.B.&M. TAKEN FROM THE RED WASH SW QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4938 FEET.



SCALE

CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

No. 5709

ROBERT L. KAY

REGISTERED LAND SURVEYOR
REGISTRATION NO. 5709
STATE OF UTAH

UINTAH ENGINEERING & LAND SURVEYING

85 SOUTH 200 EAST - VERNAL, UTAH 84078

(801) 789-1017

| | | | | | |
|---------|------------------|----------------|---------------------|-------------|---------|
| SCALE | 1" = 1000' | DATE SURVEYED: | 9-2-92 | DATE DRAWN: | 9-11-92 |
| PARTY | D.A. B.C. J.L.G. | REFERENCES | G.L.O. PLAT | | |
| WEATHER | HOT | FILE | ENRON OIL & GAS CO. | | |

EIGHT POINT PLAN

CHAPITA WELLS UNIT 350-14N

SECTION 14, T9S, R22E

UINTAH COUNTY, UTAH

RECEIVED

SEP 24 1992

DIVISION OF
OIL GAS & MINING

1. & 2. ESTIMATED TOPS & ANTICIPATED OIL, GAS & WATER ZONES:

| FORMATIONS | DEPTH | TYPE ZONES | MAXIMUM PRESSURE |
|-----------------|--------|-----------------|------------------|
| Green River | | | |
| Oil Shale | 1,527' | | |
| "H" Marker | 3,189' | | |
| "J" Marker | 3,857' | | |
| Base "M" Marker | 4,386' | | |
| Wasatch | | | |
| Peters Point | 4,782' | Gas | 2,200 PSI |
| Chapita Wells | 5,312' | Gas | 2,400 PSI |
| Buck Canyon | 5,872' | Gas | 2,600 PSI |
| Island | 6,795' | Gas | 3,100 PSI |
| EST. TD | 7,300' | Anticipated BHP | 3,300 PSI |

All depths are based on estimated KB elevation 4,935'. Maximum pressure estimates are based on bottom hole pressures measured on offset or near vicinity wells to the subject well.

3. PRESSURE CONTROL EQUIPMENT: BOP Schematic Diagram attached.

4. CASING PROGRAM:

| HOLE SIZE | INTERVAL | LENGTH | SIZE | WEIGHT | GRADE | MINIMUM SAFETY FACTOR | | |
|-----------|------------|--------|--------|--------|-----------|-----------------------|----------|----------|
| | | | | | | COLLAPSE | BURST | TENSILE |
| 12 1/4" | 0' - 240' | 240' | 9 5/8" | 32.3# | H-40 ST&C | 1400 PSI | 2270 PSI | 254,000# |
| 7 7/8" | 0' - 7300' | 7300' | 4 1/2" | 10.5# | J-55 ST&C | 4010 PSI | 4790 PSI | 146,000# |

All casing to be used will be new or inspected.

5. MUD PROGRAM:

| INTERVAL | MUD TYPE |
|--------------|--|
| 0' - 240' | Air |
| 240' - 4000' | Air/Mist & Aerated Water |
| 4000' - TD | Air/3% KCl water or KCl substitute |
| | Gel/polyacrylamide polymer w/5-10% LCM |

EIGHT POINT PLAN

CHAPITA WELLS UNIT 350-14N

PAGE NO. 2

Lost circulation probable from 1500' to 3000'±.
Sufficient mud inventory will be maintained on location during drilling to handle any adverse conditions that may arise.

6. VARIANCE REQUESTS:

- A. Enron requests a variance to regulations requiring a straight run blooie line. (There will be two targeted tees in blooie line).
- B. Enron requests a variance to regulations requiring an automatic ignitor or continuous pilot light on the blooie line. (Not required on aerated water system).

7. EVALUATION PROGRAM:

| | | |
|-------|--------------------|------------------------------------|
| Logs: | Dual Laterolog/GR | From base of surface casing to TD. |
| | FDC-CNL/GR/Caliper | TD to 3000'. |
| | Linear 2" DLL. | |

Cores: None Programmed.
DST' : None Programmed.

Completion: To be submitted at a later date.

8. ABNORMAL CONDITIONS:

None anticipated.

9. STANDARD REQUIRED EQUIPMENT:

- A. Choke Manifold
- B. Kelly Cock
- C. Stabbing Valve
- D. Visual Mud Monitoring

Attachment: BOP Schematic Diagram

CWU350-146NPP
/LW

RECEIVED

SEP 24 1992

CONDITIONS OF APPROVAL
FOR THE SURFACE USE PROGRAM OF THE
APPLICATION FOR PERMIT TO DRILL

DIVISION OF
OIL GAS & MINING

Company/Operator: Enron Oil & Gas Company
Well Name & Number: Chapita Wells Unit 350-14N
Lease Number: U-0282
Location: 660' FSL & 1980' FEL SW/SE Sec. 14 T. 9S R. 22E
Surface Ownership: Federal Lands - BLM

NOTIFICATION REQUIREMENTS

- Location Construction - forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and related Equipment Tests - twenty-four (24) hours prior to running casing and tests.
- First Production Notice - within five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

THIRTEEN POINT SURFACE USE PROGRAM

1. EXISTING ROADS

- A. See attached Wellsite Plats showing directional reference stakes on location, and attached TOPO Map "B" showing access to location from existing road.
- B. The proposed well site is located approximately 17.5 miles southeast of Ouray, Utah - See attached TOPO Map "A".
- C. Refer to attached Topographic Map "A" showing labeled access route to location.
- D. Existing roads will be maintained and repaired as necessary. No off lease Right-of-Way will be required.

2. PLANNED ACCESS ROAD

- A. The access road will be 0.2 mile in length. See attached TOPO Map "B".
- B. The access road has a 30 foot ROW w/18 foot running surface.
- C. Maximum grade on access road will be 5%.
- D. No turn outs will be required.
- E. Road drainage crossings shall be of the typical dry creek drainage crossing type.
- F. No culverts, bridges or major cuts & fills will be required.
- G. The access road will be dirt surface.
- H. No gates, cattleguards or fences will be required or encountered.

New or reconstructed roads will be centerline - flagged at time of location staking.

All travel will be confined to existing access road Right-of-Way. Access roads and surface disturbing activities will conform to standards outlined in the Bureau of Land Management and Forest Service Publication: Surface Operating Standards For Oil & Gas Exploration and Development, (1989).

The road shall be upgraded to meet the standards of the anticipated traffic flow and all-weather road requirements. Upgrading shall include ditching, drainage, graveling, crowning, and capping the roadbed as necessary to provide a well constructed safe road. Prior to upgrading, the road shall be cleared of any snow cover and allowed to dry completely. Traveling off the 30 foot Right-of-Way will not be allowed.

Road drainage crossing shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or accumulation of debris in the drainage crossings nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by run off water shall be prevented by diverting water off at frequent intervals by means of cutouts. Upgrading shall not be allowed during muddy conditions. Should mud holes develop, they shall be filled in and detours around them avoided.

No Right-of-Way applications will be required.

As operator Enron Oil & Gas Company shall be responsible for all maintenance on cattleguards, or gates associated with this oil and/or gas operation.

3. LOCATION OF EXISTING WELLS WITHIN A ONE MILE RADIUS OF PROPOSED WELL LOCATION

- A. Water wells - None.
- B. Abandoned wells - Two
- C. Temporarily abandoned wells - None
- D. Disposal wells - None
- E. Drilling wells - None
- F. Producing wells - Twelve - See attached TOPO Map "C" for location of producing wells.
- G. Shut in wells - None
- H. Injection wells - None

4. LOCATION OF EXISTING/AND OR PROPOSED FACILITIES

A. ON WELL PAD

- 1. Tank batteries - None
- 2. Production facilities will be set on location if well is successfully completed for production. Facilities will consist of well head & valves, separator, dehy, 210 BBl condensate tank, meter house and attaching piping. See attached facility diagram.
- 3. Oil gathering lines - None
- 4. A 3 1/2" gathering line will be buried from dehy to west edge of location.
- 5. Injection lines - None
- 6. Disposal lines - None
- 7. Surface pits - None

B. OFF WELL PAD

- 1. Proposed location of attendant off pad gas flowlines shall be flagged prior to archaeological clearance.
- 2. A 4 1/2" OD steel above ground natural gas pipeline will be laid approximately 400' from proposed location to a point in the SW/SE of Sec. 14, T9S, R22E where it will tie into Questar Pipeline Co.s' existing line. Proposed pipeline crosses BLM administered lands within the Chapita Wells Unit, thus no Right-of-Way grant will be required. See attached Exhibit A showing pipeline route.
- 3. Proposed gas gathering pipeline will be a 4 1/2" OD steel, welded line laid on the surface.
- 4. Protective measures and devices for livestock and wildlife will be taken and or installed where required.

If storage facilities/tank batteries are constructed on this lease, the facility/battery or the well pad shall be surrounded by a containment dike of sufficient capacity to contain, at a minimum, the entire content of the largest tank within the facility/battery, unless more stringent protective requirements are deemed necessary by the authorized officer.

The production facilities will be placed on the south side of location.

All permanent (on site for six months or longer) structures constructed or installed (including pumping units) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Rocky Mountain Five State Interagency Committee. All facilities required will be painted within 6 months of installation. Facilities required to comply with O.S.H.A. (Occupational Safety and Health Act) will be excluded.

The required paint color is Carlsbad Canyon.

If at any time the facilities located on public land and authorized by the terms of the lease are no longer included in the lease (due to a contraction in the unit or other lease or unit boundary change), BLM will process a change in authorization to the appropriate rental or other financial obligation as determined by the authorized officer.

5. LOCATION & TYPE OF WATER SUPPLY

- A. Water supply will be from Ouray Brine Plant at Ouray, Utah, and/or Target Trucking Inc.s' water source in the SW/SW Sec. 35, T9S, R22E, Uintah County, Utah (State water right #49-1501).
- B. Water will be hauled by Target Trucking Inc.
- C. No water well will be drilled on lease.

6. SOURCE OF CONSTRUCTION MATERIAL

- A. All construction material for this location and access road will be of native borrow and soil accumulated during the construction of location.
- B. All construction material will come from Federal Land.
- C. No mineral materials will be required.

7. METHODS OF HANDLING WASTE DISPOSAL

A. METHODS AND LOCATION

- 1. Cuttings will be confined in the reserve pit.
- 2. A portable toilet will be provided for human waste during the drilling and completion of the well. Disposal will be at the Vernal sewage disposal plant.
- 3. Burning will not be allowed. Trash and other waste material will be contained in a wire mesh cage and disposed of at an approved waste disposal facility.
- 4. Produced waste water will be confined to a lined pit or storage tank for a period not to exceed 90 days after initial production. During the 90 days period, an application for approval of a permanent disposal method and location, together with the required water analysis, will be submitted for the AO's approval.
- 5. All chemicals will be disposed of at an authorized disposal site. Drip pans and absorbent pads will be used on drilling rig to avoid leakage of oil to pit.

- B. Water from drilling fluids and recovered during testing operations will be disposed of by either evaporating in reserve pit or be removed and disposed of at an authorized disposal site. Introduction of well bore hydrocarbons to reserve pit will be avoided by flaring them off in flare pit at time of recovery.

Burning will not be allowed. all trash must be contained in a trash cage and hauled away to an approved disposal site at the completion of the drilling activities.

On BLM administered land:

The reserve pit will be constructed so as not to leak, break, or allow discharge. The reserve pit shall not be lined unless required by construction. The pit will be inspected prior to adding fluids.

After first production, produced waste water will be confined to a lined pit or storage tank for a period not to exceed ninety (90) days. During the 90 day period, in accordance with NTL-2B, an application for approval of a permanent disposal method and location, along with required water analysis, shall be submitted for the AO's approval. Failure to file an application within the time allowed will be considered an incident of noncompliance.

8. ANCILLARY FACILITIES

- A. No airstrips or camps are planned for this well.

9. WELL SITE LAYOUT

- A. Refer to attached well site plat for related topography cuts and fills & cross sections.
B. Refer to attached well site plat for rig layout and soil material stockpile location as approve on On-site.
C. Refer to attached well site plat for rig orientation parking areas, and access road.

The reserve pit will be located on the northwest side of location.

The flare pit will be located downwind of the prevailing wind direction on the north side of location a minimum of 100 feet from the well head and 30 feet from the reserve pit fence.

The stockpiled topsoil will be stored on the west side.

Access to the well pad will be from the east.

1 Diversion ditch shall be constructed on the south side of the location below the cut slope, draining to the east and west.

NA Soil compacted earthen berm(s) shall be placed on the _____ side(s) of the location between the _____

NA The drainage(s) shall be diverted around the side(s) of the well pad location.

NA The reserve pit and/or pad locations shall be constructed long and narrow for topographic reasons _____.

The southeast corner of the well pad will be rounded off to minimize the necessary cut.

FENCING REQUIREMENTS

All pits will be fenced according to the following minimum standards:

- A. 39 inch net wire shall be used with at least one strand of barbed wire on top of the net wire. (barbed wire is not necessary if pipe or some type of reinforcement rod is attached to the top of the entire fence).
- B. The net wire shall be no more than 2 inches above the ground. The barbed wire strand shall be 3 inches above the net wire. Total eight of the fence shall be at least 42 inches.
- C. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
- D. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than 16'.
- E. All wire shall be stretched by using a stretching device before is be attached to the corner posts.

The reserve pit fencing will be on the three sides during drilling operations and on the fourth side when the rig moves off the location. Pits will be fenced and maintained until clean-up.

Each existing fence to be crossed by the access road shall be braced and tied off before cutting so as to prevent slacking of the wire. The opening shall be closed temporarily as necessary during construction to prevent the escape of livestock, and upon completion of construction the fence shall be repaired to BLM or SMA specifications. A cattleguard with an adjacent 16 foot gate shall be installed in any fence where a road is to be regularly travelled. If the well is a producer, the cattleguards (shall/shall not) be permanently mounted on concrete bases. Prior to a new road, crossing any fence located on federal land, or any fence between federal land and private land, the operator will contact the BLM, who will in turn contact the grazing permittee or owner of said fence and offer him/her the opportunity to be present when the fence is cut in order to satisfy himself/herself that the fence is adequately braced and tied off.

10. PLANS FOR RESTORATION OF SURFACE

A. PRODUCING LOCATION

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, materials, trash, and junk not required for production.

Immediately upon well completion, any hydrocarbons on the pit shall be removed in accordance with CFR 3162.7-1.

If a plastic nylon reinforced liner is used, it shall be torn and perforated before backfilling of the reserve pit.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 12 months from the date of well completion. Before any dirt work takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc., will be removed.

Contact appropriate surface management agency for required seed mixture.

B. DRY HOLE/ABANDONED LOCATION

At such time as the well is plugged and abandoned, the operator will submit a subsequent report of abandonment and BLM will attach the appropriate surface rehabilitation conditions of approval.

11. SURFACE OWNERSHIP

Access road: Federal
Location: Federal

12. OTHER INFORMATION

- A. Enron Oil & Gas Company will inform all persons in the area who are associated with this project that they are subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, the operator will immediately stop work that might further disturb such materials, and contact the AO. Within five working days the AO will inform the operator as to:

-whether the materials appear eligible for the National Register of historic Places;

-the mitigation measures the operator will likely have to undertake before the site can be used.

-a time frame for the AO to complete an expedited review under 36 CFR 800.11 to confirm, through the State Historic Preservation Officer, that the findings of the AO are correct and that mitigation is appropriate.

-if the operator wishes, at any time, to relocate activities to avoid the expense of mitigation and/or the delays associated with this process, the AO will assume responsibility for whatever recordation and stabilization of the exposed materials may be required. Otherwise, the operator will be responsible for mitigation costs. The AO will provide technical and procedural guideline for the conduct of mitigation. Upon verification from the AO that required mitigation has been completed, the operator will then be allowed to resume construction.

- B. As operator Enron Oil & Gas Company will control noxious weeds along Right-of-Ways for roads, pipelines, well sites or other applicable facilities. A list of noxious weeds will be obtained from the BLM, or the appropriate County Extension Office. On BLM administered land a Pesticide Use proposal shall be submitted, and given approval, prior to the application of herbicides or other pesticides or possible hazardous chemicals.

- C. Drilling rigs and/or equipment used during drilling operations on this wellsite will not be stacked or stored on Federal Lands after the conclusion of drilling operations or at any other time without BLM authorization. However, if BLM authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities. (The BLM does not seek to compete with private industry. There are commercial facilities available for stacking and storing drilling rigs.)

Additional Surface Stipulations

NA No construction or drilling activities shall be conducted between _____ and _____ because of _____

NA No surface occupancy will be allowed within 1,000 feet of any sage grouse strutting ground.

NA No construction or exploration activities are permitted within 1.5 mile radius of sage grouse strutting grounds from April 1 to June 30.

NA There shall be no surface disturbance within 600 feet of live water (includes stock tanks, springs, and guzzlers).

NA No cottonwood trees will be removed or damaged.

1 Pond will be constructed according to BLM specifications approximately 300 ft. northeast of the location, as flagged on onsite.

LESSEE'S OR OPERATORS REPRESENTATIVE AND CERTIFICATION

Enron Oil and Gas Company
P.O. Box 1815
Vernal, Utah 84078
George McBride
Telephone: (801) 789-0790

Enron Oil and Gas Company
P.O. Box 250
Big Piney, Wyoming
Jim Schaefer
Telephone: (307) 276-3331

All lease/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approval plan of operations, and any applicable Notice to Lessees. Enron Oil & Gas Company is fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to the field representative to insure compliance.

A copy of the approved APD and ROW grant, if applicable, shall be on location during construction of the location and drilling activities

The BLM Office shall be notified upon site completion prior to moving on the drilling rig.

Certification:

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drillsite and access route; that I am familiar with the conditions which presently exist; that the statements made in the Plan are to the best of my knowledge, true and correct; and that the work associated with the operations proposed here in will be performed by ENRON OIL & GAS COMPANY and its contractors and sub-contractors in conformity with this Plan and the terms and conditions under which it is approved.

September 17, 1992
DATE



GEORGE R. MCBRIDE
SR. PRODUCTION FOREMAN

1w
CWU350-14NPP


2000 PSIG BOP DIAGRAM

ANNULAR PREVENTOR AND BOTH RAMS ARE 3000 PSIG RATED.
CASING FLANGE IS 11" 3000 PSIG RATED.
BOPE 11" 2000 PSIG


TESTING PROCEDURE:

1. BOPE's will be tested with a professional tester to conform to Onshore Order #2 with retest every 14 days.
2. Blind & Pipe rams will be tested to rated working pressure, 2000 psig.
3. Annular preventor will be tested to 50% of working pressure, 1500 psig.
4. Casing will be tested to 0.22 psi/ft. or 1500 psig. Not to exceed 70% of burst strength, whichever is greater.
5. All lines subject to well pressure will be pressure tested to the same pressure as blind & pipe rams.
6. All BOPE specifications and configurations will meet Onshore Order #2 requirements for 2000 psig BOPE specifications.

H:\DOC\BOP\TAH.DIA



CHAPITA WELLS UNIT 350-14N
SECTION 14, T9S, R22E
UINTAH COUNTY, UTAH
FEDERAL LEASE #U-0282



CWU350-14N/lw




EXHIBIT "A"
GAS SALES PIPELINE

SCALE: 1" = 2000'
 DATE 9-11-92 J.L.G.



ENRON OIL & GAS CO.

CWU #350-14
 SECTION 14, T9S, R22E, S.L.B.&M.

DRILLING PROGRAM

Date: August 29, 1992

REVISION NO. & DATE: _____

PROSPECT: CHAPITA WELLS UNIT LEASE: U-0282

WELL NAME & NUMBER: Chapita Wells Unit 350-14N

WELL CLASSIFICATION: DW-GAS ANTICIPATED PRODUCTION: OIL _____ GAS X OTHER _____
TGS X

LOCATION CALL: 660' FSL & 1980' FEL (SW SE)
Section 14, T9S, R22E
Uintah County, Utah

ELEVATION: 4920' GL, 4934' KB (estimated)

DIRECTION LIMITATIONS: Maximum deviation for the hole will be 6° w/no more
than a 1°/100' dogleg severity. See page number 4 for distance between
surveys.

TYPE RIG: Land Rotary APPROVED DEPTH: 7300' PERMIT DEPTH: 7300'

CONDUCTOR NEEDED? No If yes, size & how set: _____

CRITERIA FOR DETERMINING CASING SEAT FOR CRITICAL STRINGS: WOC overnight
before cutting off surface casing to weld on head.

CENTRALIZERS (DEPTH & TYPE):

Surface - One 5-10' above shoe & top of first, second & fourth joint.

Production - One @ middle of 1st jt & every third collar to 4700'±.

RECEIVED

SEP 24 1992

DIVISION OF
OIL GAS & MINING

WELL NAME: Chapita Wells Unit 350-14N

STAGE COLLARS, BASKETS, OTHER SPECIAL EQUIPMENT:

Surface - Guide shoeProduction - Guide shoe and differential fill float collar with top plug.

Marker joints @ 3000'± and 5000'±.

PUMPING RATES/SPECIAL INSTRUCTIONS: Circulate casing two hours prior to cementing. Reciprocate casing.LOGGING PROGRAM: DLL/GR from TD to base of surface casing.FDC/CNL/GR/caliper from TD to 100' above Green River "H" Marker.Continue caliper to desired top of cement.CORES: None are anticipated.SAMPLES: Collect 30' samples from below surface casing to 4300'±. Collect 10' samples from 4300'± to TD.FORMATION TESTS: None are anticipated.MUD LOGGING: (Includes services & depth): From 4300'± to TD.DETECTION & CONTROL EQUIPMENT: 10" 2000 psig BOP with blind and pipe rams.10" Annular Preventor. 10" rotating head. Test manifold & BOP's to 2000 psig, annular preventor to 1500 psig, surface casing to 1500 psig.Use certified pressure testing service company and leave a copy of the test chart in the doghouse until rig down.COMPLETION PROGRAM: To be submitted at a later date.OTHER SERVICES: None are anticipated.

WELL NAME: Chapita Wells Unit 350-14NFORMATION TOPS & DEPTHS (TENTATIVE)

| FORMATION NAME & TYPE | ESTIMATED DEPTH (EL) | DATUM | THICKNESS & REMARKS |
|-----------------------|----------------------|-------|---------------------|
|-----------------------|----------------------|-------|---------------------|

See attached Prognosis.

X-MAS TREE: 10" 3000# weld on casing head, 6" 5000# x 10" 3000# tubing
spool, 2-1/16" 5000# master valves.

MUD PROGRAM

| DEPTH INTERVAL | MUD WEIGHT | VIS | WL (cc) | TYPE OF MUD |
|----------------|------------|-------|---------|---|
| 0' to 240' | | | | Air |
| 240' to 4000' | | | | Air/Mist & Aerated Water |
| 4000' to TD | | | | Aerated 3% KCl water or KCl substitute. |
| TD | 8.5-9.2 | 38-45 | 10-15 | Gel/polyacrylamide polymer w/5-10% LCM. |

DRILLING HAZARDS & SPECIAL INSTRUCTIONS

Lost circulation from 1500' to 3000'+. Underbalanced circulation system will require rotating head. Potential gas kicks in Green River and Wasatch. Potential shale swelling/sloughing problems. Meter air & add foamer to maximize consistency of returns & maintain stable pit levels. Utilize pack off head while running open hole logs. Mix 700-800 bbls mud @ TD as above & displace hole prior to tripping for logs.

WELL NAME: Chapita Wells Unit 350-14N

CEMENT PROGRAM

| HOLE SIZE | CASING SIZE | DEPTH | CEMENT PROCEDURE |
|--------------------|-------------------|-------|--|
| 12 $\frac{1}{4}$ " | 9" | 240' | Cement w/110 sx Class "G" cement + 2% CaCl ₂ + $\frac{1}{4}$ #/sx celloflake. Circulate gelled water ahead of slurry. |
| 7 $\frac{1}{2}$ " | 4 $\frac{1}{2}$ " | 7300' | Cover interval from TD to 4500'± w/50/50 Pozmix + 2% gel + 10% salt. Volume to be calculated from caliper log annular volume to 4500' plus 10% excess. Cover interval from 4500'± to depth specified in conditions of approval with light cement plus specified additives. Volume to be calculated from caliper log annular volume from 4500'± to applicable upper depth plus 5% excess. Circulate casing 2 hrs before cementing. Reciprocate casing during cementing. Pump 10 bbls mud flush ahead of slurry. |

CASING PROGRAM

| INTERVAL | | | | WEIGHT | | | MINIMUM SAFETY FACTOR | | |
|----------|------|-------|--------|--------|-------|--------|-----------------------|--------------|----------------|
| SIZE | FROM | TO | LENGTH | #/FT. | GRADE | THREAD | COLLAPSE (psig) | BURST (psig) | TENSILE (psig) |
| 9-5/8" | 0' | 240' | 240' | 32.3# | H-40 | ST&C | 1400 | 2270 | 254,000 |
| 4-1/2" | 0' | 7300' | 7300' | 10.5# | J-55 | ST&C | 4010 | 4790 | 146,000 |

SURVEY SCHEDULE



| DEPTH | DISTANCE BETWEEN SURVEYS | MAX DEVIATIONS FROM VERTICAL | MAXIMUM CHANGE DEGREES/100' |
|------------|--------------------------|------------------------------|-----------------------------|
| 0' to 240' | 240' | 1 degree | 1 degree |
| 240' to TD | 500' (or as needed) | 6 degrees | 1 degree |

PREPARED BY: Jim R. Schaefer, Sr. Production Engineer

APPROVED BY: Dennis J. Brabec, Drilling Superintendent


APPROVED BY: C. C. Parsons, District Manager

ENRON OIL & GAS CO.
LOCATION LAYOUT FOR
CWU #350-14
SECTION 14, T9S, R22E, S.L.B.&M.



TYP. LOCATION LAYOUT


TYP. CROSS SECTIONS



Elev. Ungraded Ground at Location Stake = 4923.5'

Elev. Graded Ground at Location Stake = 4923.0'

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East Vernal, Utah




TOPOGRAPHIC
MAP "A"

DATE 9-11-92 J.L.G.



ENRON OIL & GAS CO.

CWU #350-14
SECTION 14, T9S, R22E, S.L.B.&M.




TOPOGRAPHIC
MAP "B"

SCALE: 1" = 2000'
DATE 9-11-92 J.L.G.



ENRON OIL & GAS CO.

CWU #350-14
SECTION 14, T9S, R22E, S.L.B.&M.



LEGEND:

- = Water Wells
- = Abandoned Wells
- = Temporarily Abandoned Wells
- = Disposal Wells
- = Drilling Wells
- = Producing Wells
- = Shut-in Wells



ENRON OIL & GAS CO.

CWU #350-14

SECTION 14, T9S, R22E, S.L.B.&M.

TOP O MAP "C"

DATE: 9-11-92 J.L.G.

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

DATE RECEIVED: 09/24/92

OPERATOR: ENRON OIL & GAS COMPANY
WELL NAME: CWU 350-14N

OPERATOR ACCT NO: N- 0401

API NO. ASSIGNED: 43-047-30375

LEASE TYPE: FED LEASE NO: U-0080
LOCATION: SWSE 14 - T09S - R22E UINTAH COUNTY
FIELD: NATURAL BUTTES FIELD CODE: 630

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond
(Number 49-1501)
☒ Potash (Y/N) (N)
☒ Oil shale (Y/N) (N)
☒ Water permit
(Number 49-1501)
☒ RDCC Review (Y/N) (N)
(Date: _____)

LOCATION AND SITING:

☒ R649-2-3. Unit: Chapita Wells
☐ R649-3-2. General.
☐ R649-3-3. Exception.
☐ Drilling Unit.
Board Cause no: _____
Date: _____

COMMENTS: Included in 90 PDD approved 9.00.90

Oil shale area
PDD does not include "N" in well name and
thus does not require BLM 4-08-90.

STIPULATIONS:

Oil Shale



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Norman H. Bangerter
Governor

Dee C. Hansen
Executive Director

Dianne R. Nielson, Ph.D.
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340

September 29, 1992

Enron Oil and Gas Company
P.O. Box 1815
Vernal, Utah 84078

Gentlemen:

Re: Chapita Wells Unit 350-14N Well, 660 feet from the south line, 1980 feet from the east line, SW 1/4 SE 1/4, Section 14, Township 9 South, Range 22 East, Uintah County, Utah

Pursuant to Utah Code Ann. § 40-6-18, (1953, as amended), Utah Admin. R. 649-2-3, Application of Rules to Unit Agreements and R. 649-3-4, Permitting of Wells to be Drilled, Deepened or Plugged-Back, approval to drill the referenced well is hereby granted.

In addition, the following specific actions are necessary to fully comply with this approval:

1. Compliance with the requirements of Utah Admin. R. 649-1 et seq., Oil and Gas Conservation General Rules.
2. Notification within 24 hours after drilling operations commence.
3. Submittal of Entity Action Form, Form 6, within five working days following commencement of drilling operations and whenever a change in operations or interests necessitates an entity status change.
4. Submittal of the Report of Water Encountered During Drilling, Form 7.
5. Prompt notification prior to commencing operations, if necessary, to plug and abandon the well. Notify Frank R. Matthews, Petroleum Engineer, (Office) (801)538-5340, (Home) (801)476-8613, or R.J. Firth, Associate Director, (Home) (801)571-6068.

Page 2

Enron Oil and Gas Company

Chapita Wells Unit 350-14N Well

September 29, 1992

6. Compliance with the requirements of Utah Admin. R. 649-3-20, Gas Flaring or Venting, if the well is completed for production.

Trash and sanitary waste should be properly contained and transported to approved disposal locations, not retained in or disposed of in pits on location or downhole. Prior to the commencement of drilling operations, the operator should consult the local/county sanitarian and/or the Department of Environmental Quality, Division of Drinking Water/Sanitation, regarding appropriate disposal of sanitary waste.

This approval shall expire one year after date of issuance unless substantial and continuous operation is underway or a request for an extension is made prior to the approval expiration date. The API number assigned to this well is 43-047-32375.

Sincerely,



R.J. Firth

Associate Director, Oil and Gas

Idc

Enclosures

cc: Bureau of Land Management

J.L. Thompson

WO11

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒

DEEPEN ☐

PLUG BACK ☐

b. TYPE OF WELL

OIL
WELL ☐

GAS
WELL ☒

OTHER

SINGLE
ZONE ☐

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Enron Oil & Gas Company

3. ADDRESS OF OPERATOR

P.O. Box 1815, Vernal, Utah 84078

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements)
At surface

660' FSL & 1980' FEL SW/SE

At proposed prod. zone

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

17.9 Miles Southeast of Ouray, Utah

15. DISTANCE FROM PROPOSED*

LOCATION TO NEAREST
PROPERTY OR LEASE LINE, FT.
(Also to nearest drilg. unit line, if any)

3300'

18. DISTANCE FROM PROPOSED LOCATION*

TO NEAREST WELL, DRILLING, COMPLETED,
OR APPLIED FOR, ON THIS LEASE, FT.

1310'

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

4923' Graded Ground

23. PROPOSED CASING AND CEMENTING PROGRAM

| SIZE OF HOLE | SIZE OF CASING | WEIGHT PER FOOT | SETTING DEPTH | QUANTITY OF CEMENT |
|--------------|----------------|-----------------|---------------|------------------------------|
| 12 1/4" | 9 5/8" | 32.3# | 240' | 125 sx Class "G" + 2% CaCl2 |
| 7 7/8" | 4 1/2" | 10.5# | 7300' | + 1/4 #/sx celloflake. 50/50 |
| | | | | Pozmix + 2% gel + 10% salt |
| | | | | to 400' above all zones of |
| | | | | interest (+ 10% excess). |
| | | | | Light cement (11 PPG±) |
| | | | | + LCM to 200' above oil |
| | | | | shale or fresh water |
| | | | | intervals (+ 5% excess). |

SEE ATTACHMENTS FOR:

8 Point Plan
Drilling Program
BOP Schematic
Surface Use and Operating Plan
Location Plat
Location Layout
Topographic Maps "A", "B", and "C"
Gas Sales Pipeline Exhibit "A"

RECEIVED

SEP 17 1992

Enron Oil & Gas Company will be the
designated operator of the subject well
under Nation Wide Bond #81307603.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM: If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24.

SIGNED

Linda L. Wallace

TITLE

Sr. Admin. Clerk

DATE

9/17/92

(This space for Federal or State office use)

PERMIT NO.

APPROVAL DATE

APPROVED BY

[Signature]

TITLE

ASSISTANT DISTRICT
MANAGER MINERALS

DATE

OCT 14 1992

CONDITIONS OF APPROVAL, IF ANY:

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

NOTICE OF APPEAL

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Div 06vM

WELL LOCATION INFORMATION

Company/Operator: Enron Oil & Gas Company

API Number: 43-047-32375

Well Name & Number: CWU 350-14N

Lease Number: U-0282

Location: SWSE Sec. 14 T. 9S R. 22E

Surface Ownership: Federal Lands administered by BLM

Date NOS Received: September 14, 1992

Date APD Received: September 17, 1992

NOTIFICATION REQUIREMENTS

- | | | |
|---------------------------------|---|---|
| Location Construction | - | at least forty-eight (48) hours prior to construction of location and access roads. |
| Location Completion | - | prior to moving on the drilling rig. |
| Spud Notice | - | at least twenty-four (24) hours prior to spudding the well. |
| Casing String and Cementing | - | at least twenty-four (24) hours prior to running casing and cementing all casing strings. |
| BOP and Related Equipment Tests | - | at least twenty-four (24) hours prior to initiating pressure tests. |
| First Production Notice | - | within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days. |

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for a 2M system for equipment and testing requirements, procedures, etc., and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the top of the Mahogany oil shale zone, identified at \pm 750 ft. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to \pm 550 ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the

date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-2, 3162.7-3, and 3162.7-4 shall be submitted to the appropriate District Office within thirty (30) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-4.

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling onlease or off-lease will have prior written approval from the AO.

Gas meter runs for each well will be located within 500 feet of the wellhead. The gas flowline will be buried or anchored down from the wellhead to the meter and within 500 feet downstream of the meter run or any production facilities. Meter runs will be housed and/or fenced.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted monthly for the first three months on new meter installations and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approvals are necessary, please contact one of the following individuals:

Gerald E. Kenczka (801) 781-1190
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

BLM FAX Machine (801) 789-3634

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

Unused fracturing fluids or acids

Gas plant cooling tower cleaning wastes

Painting wastes

Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids

Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste

Refinery wastes

Liquid and solid wastes generated by crude oil and tank bottom reclaimers

Used equipment lubrication oils

Waste compressor oil, filters, and blowdown

Used hydraulic fluids

Waste solvents

Waste in transportation pipeline-related pits

Caustic or acid cleaners

Boiler cleaning wastes

Boiler refractory bricks

Incinerator ash

Laboratory wastes

Sanitary wastes

B. SURFACE USE PROGRAM

1. Plans for Restoration of Surface

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximate natural contours. The reserve pit will be reclaimed within 90 days from the date of well completion. Before any dirt work takes place, the reserve pit must be completely dry and all cans, barrels, pipe, etc., will be removed.

DIVISION OF OIL, GAS AND MINING

SPUDDING INFORMATION

NAME OF COMPANY: ENRON 43-047-32375

WELL NAME: CHAPITA WELLS 350-14N

Section 14 Township 9S Range 22E County UINTAH

Drilling Contractor VECO

Rig # 6

SPUDDED: Date 10/28/92

Time NOON

How DRY HOLE

Drilling will commence

Reported by KENT STRINGHAM

Telephone # 1-828-7677

Date 10/30/92 SIGNED MKH

ENTITY ACTION FORM - FORM 6

ADDRESS P.O. BOX 1815Vernal, Utah 84078

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|-------------|--------------------|----------------|--------------|------------------------|---------------|----|-----|-----|--------|-----------|----------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| A | 99999 | 11439 | 43-047-32377 | WILDHORSE FEDERAL 3-26 | SWNW | 26 | 10S | 19E | Uintah | 10/25/92 | 10/25/92 |

WELL 1 COMMENTS:

Entities added 11-3-92. *for*

| | | | | | | | | | | | |
|---|-------|---|--------------|----------------------------|------|----|----|-----|--------|----------|----------|
| B | 04905 | → | 43-047-32375 | CHAPITA WELLS UNIT 350-14N | SWSE | 14 | 9S | 22E | Uintah | 10/27/92 | 10/27/92 |
|---|-------|---|--------------|----------------------------|------|----|----|-----|--------|----------|----------|

WELL 2 COMMENTS:

"

| | | | | | | | | | | | |
|---|-------|---|--------------|--------------------------|------|---|----|-----|--------|----------|----------|
| B | 04905 | → | 43-047-32318 | CHAPITA WELLS UNIT 334-2 | NESW | 2 | 9S | 22E | Uintah | 08/19/92 | 08/19/92 |
|---|-------|---|--------------|--------------------------|------|---|----|-----|--------|----------|----------|

WELL 3 COMMENTS:

Entity previously added 10-9-92. *for*

| | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|

WELL 4 COMMENTS:

| | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|
| | | | | | | | | | | | |
|--|--|--|--|--|--|--|--|--|--|--|--|

WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

RECEIVED

OCT 30 1992

DIVISION OF
OIL GAS & MININGLinda L. White
SignatureSr. Admin. Clerk 10/29/92
Title Date

Phone No. (801) 789-0790

ENRON

Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

October 29, 1992

Mr. Ed Forsman
Bureau Of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078


RE: CHAPITA WELLS UNIT 350-14N
LEASE: U-0282
SWSE, SEC. 14, T9S, R22E
UINTAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Sundry notice of spudding of the referenced well.

If further information is required, please contact this office.

Sincerely,


C.C. Parsons
District Manager

jh

cc: UOG&M
D. Weaver
T. Miller
J. Tigner - 2043
Vernal Office
File

RECEIVED

NOV 02 1992

DIVISION OF
OIL GAS & MINING

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires September 30, 1990

SUNDRY NOTICE AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT --" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil WELL ☒ Gas Well ☐ Other

2. Name of Operator

ENRON OIL & GAS COMPANY

3. Address and Telephone No.

P.O. BOX 250, BIG PINEY, WY 83113 (307) 276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

**660' FSL - 1980' FEL (SW/SE)
SECTION 14, T9S, R22E**

5. Lease Designation and Serial No.
U-0282

6. If Indian, Allottee or Tribe Name

7. If Unit or C.A., Agreement Designation

CHAPITA WELLS UNIT

8. Well Name and No.

CHAPITA WELLS UNIT 350-14N

9. API Well No.

43-047-32375

10. Field and Pool or Exploratory Area
CWU/WASATCH

11. COUNTY STATE

UINTAH UTAH

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☐ NOTICE OF INTENT
☒ SUBSEQUENT REPORT
☐ FINAL ABANDONMENT NOTICE

TYPE OF ACTION

☐ ABANDONMENT
☐ RECOMPLETION
☐ PLUGGING BACK
☐ CASING REPAIR
☐ ALTERING CASING
☒ OTHER **Spudding**
☐ CHANGE OF PLANS
☐ NEW CONSTRUCTION
☐ NON-ROUTINE FRACTURING
☐ WATER SHUT-OFF
☐ CONVERSION TO INJECTION

(Note: Report results of multiple completion on Well Completions
or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details and give pertinent dates, including estimated date of starting any proposed work if well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work).

**Enron Oil & Gas Company spudded 12-1/4" surface hole at the subject location at 3:00 PM on 10/27/92.
Ed Forsman, of the Vernal BLM District office was notified of spud by telephone on 10/27/92.**

RECEIVED

NOV 02 1992

**DIVISION OF
OIL, GAS & MINING**

14. I hereby certify that the foregoing is true and correct

SIGNED Jarvis Hansen TITLE Engineering Clerk DATE 10/29/92

(This space for Federal or State office use)

APPROVED BY _____ TITLE _____ DATE _____

CONDITIONS OF APPROVAL, IF ANY:



Exploration & Production
North America

Conoco Inc.
800 Werner Court
Casper, Wyoming 82601
(307) 261-7920
(307) 261-7917 FAX

Division of State Lands & Forestry
3 Triad Center #400
Salt Lake City, UT 84180-1204

January 8, 1993

Atten: Claudia Silverhuff

RE: Request for PIN Numbers
Chapita Wells Unit Area

| | | |
|--|----------------------|----------------|
| Post-It™ brand fax transmittal memo 7671 | | # of pages > 1 |
| To: Claudia Silverhuff | From: DeAnn Anderson | |
| Co. Utah State | Co. Conoco | |
| Dept. | Phone # 261-7920 | |
| Fax # (801) 355-0922 | Fax # 307-261-7917 | |

Dear Ms. Silverhuff:

Per your request, I have listed below the wells and corresponding API numbers. Please assign PIN numbers and call me or fax them to be as soon as they have been assigned. Cathy Mora in our Ponca City office will re-send the check the State of Utah returned to Conoco.

| <u>Well Name & Number</u> | <u>API Number</u> | <u>Well Name & Number</u> | <u>API Number</u> |
|--|-------------------|-------------------------------|----------------------------------|
| <u>9S 22E Sec. 27</u> Chapita Wells Unit 306 | 4304732175 | Chapita Wells Unit 307 | 4304732176 <u>9S 22E Sec. 28</u> |
| <u>9S 22E Sec. 21</u> Chapita Wells Unit 308 | 4304732200 | Chapita Wells Unit 311 | 4304732180 <u>9S 22E Sec. 26</u> |
| <u>9S 22E Sec. 22</u> Chapita Wells Unit 324 | 4304732208 | Chapita Wells Unit 326 | 4304732277 <u>9S 22E Sec. 24</u> |
| <u>9S 22E Sec. 23</u> Chapita Wells Unit 327 | 4304732319 | Chapita Wells Unit 334 | 4304732318 <u>9S 22E Sec. 2</u> |
| <u>9S 22E Sec. 9</u> Chapita Wells Unit 337 | 4304732414 | Chapita Wells Unit 339 | 4304732206 <u>9S 22E Sec. 24</u> |
| <u>9S 22E Sec. 21</u> Chapita Wells Unit 341 | 4304732371 | Chapita Wells Unit 342 | 4304732100 <u>9S 22E Sec. 26</u> |
| <u>9S 22E Sec. 15</u> Chapita Wells Unit 343 | 4304732369 | Chapita Wells Unit 344 | 4304732370 <u>9S 22E Sec. 27</u> |
| <u>9S 22E Sec. 9</u> Chapita Wells Unit 345 | 4304732372 | Chapita Wells Unit 346 | 4304732368 <u>9S 22E Sec. 26</u> |
| <u>9S 22E Sec. 26</u> Chapita Wells Unit 347 | 4304732367 | Chapita Wells Unit 348 | 4304732373 <u>9S 22E Sec. 23</u> |
| <u>9S 22E Sec. 27</u> Chapita Wells Unit 349 | 4304732374 | Chapita Wells Unit 350 | 4304732375 <u>9S 22E Sec. 14</u> |
| <u>9S 22E Sec. 15</u> Chapita Wells Unit 351 | 4304732390 | Stagecoach Unit 41-20 | 4304732280 <u>9S 22E Sec. 26</u> |

Please contact me if you have any questions, and thank you for your help in this matter.

Sincerely,

DeAnn Anderson
DeAnn Anderson
Analyst - Land & Joint Interest

cc: Central File, Blue File

dja:\010893b.wp



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF STATE LANDS AND FORESTRY

Norman H. Bangerter
Governor

Dee C. Hansen
Executive Director

Richard J. Mitchell
Division Director

355 West North Temple
3 Triad Center, Suite 400
Salt Lake City, Utah 84180-1204
801-538-5508
801-355-0922 (Fax)

MEMORANDUM

To: Lisha Romero
From: Claudia J. Silver-Huff
Date: January 12, 1992
Re: Pen 4905

Pursuant to our conversation last week, please find attached the list of wells which should be assigned a new pen number. These wells are currently a part of pen 4905. State Lands is requesting the new number for these wells even though they are included in the same participating area of the Chapita Wells Unit as covered by pen 4905. Two of the payors of these wells owe the State a different proportion of the division order interest in these wells than in the other wells under 4905, and the State Lands computer system cannot accommodate two different entries for the same commodity from the same payor.

If you have any further questions about this matter, please give me a call.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM - FORM 6

OPERATOR ENRON OIL & GAS CO.

OPERATOR ACCT. NO. N 0401

ADDRESS P. O. BOX 250

BIG PINEY, WY 83113

(307)276-3331 (JACKIE BRAUSE)

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|--|--------------------|----------------|--------------|---------------------|---------------|----|----|-----|--------|-----------|----------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| D | 04905 | 11455 | | *SEE ATTACHED LIST* | | | | | | | 1-12-93 |
| WELL 1 COMMENTS: *UPDATED 1-12-93 / CHAPITA WELLS UNIT "WSTC BCDE" P.A. (THIS CHANGE DOES NOT AFFECT ALL WELLS WITHIN SAME PARTICIPATING AREA) | | | | | | | | | | | |
| D | 04920 | 11456 | 43-047-32280 | STAGECOACH 41-20 | NENE | 20 | 9S | 22E | UINTAH | 7-30-92 | 1-12-93 |
| WELL 2 COMMENTS: *UPDATED 1-12-93 / STAGECOACH UNIT "WSTC" P.A. (THIS CHANGE DOES NOT AFFECT ALL WELLS WITHIN SAME PARTICIPATING AREA) | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 3 COMMENTS: *NOTIFIED ENRON OIL & GAS (WYOMING & VERNAL OFFICE) OF CHANGES. | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 4 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 5 COMMENTS: | | | | | | | | | | | |

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

L. ROMERO (DOGM)

Signature

ADMIN. ANALYST

1-12-93

Title

Date

Phone No. ()

ENRON
OIL & GAS COMPANY

P.O. BOX 1815, VERNAL, UTAH 84078 (801)789-0790

January 18, 1993

Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

RE: Chapita Wells Unit 350-14N
Sec. 14, T9S, R22E
Uintah County, Utah


Attn: Ed Forsman:

Dear Mr. Forsman:

Please find attached 3 (three) Sundry Notices requesting approval for water disposal method.

If you have any questions or need additional information, please contact this office.

Very truly yours,
ENRON OIL & GAS COMPANY



George R. McBride
Sr. Production Foreman

cc: Division of Oil Gas & Mining
Big Piney Office
Doug Weaver/Toni Miller
Suzanne Saldivar - Houston
Diane Cross - Houston
File

/lwSundry

RECEIVED

JAN 20 1993

DIVISION OF
OIL GAS & MINING

(November 1983),

(Formerly 9-331)

**UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT**

SUBMIT IN TRIPLICATE

(Other instruction on reverse side)

Form approved.

Budget Bureau No. 1004-0135

Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT-" for such proposals.)

1. OIL WELL ☐ GAS WELL ☒ OTHER ☐

2. NAME OF OPERATOR

ENRON OIL & GAS COMPANY

3. ADDRESS OF OPERATOR

P.O. BOX 1815, VERNAL, UTAH 84078

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.*
See also space 17 below.)

At surface

660' FSL & 1980' FEL SW/SE5. LEASE DESIGNATION AND SERIAL NO.
U-0282

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

7. UNIT AGREEMENT NAME
CHAPITA WELLS UNIT8. FARM OR LEASE NAME
CHAPITA WELLS UNIT

9. WELL NO.

350-14N

10. FIELD AND POOL OR WILDCAT

CWU/WASATCH

11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA

SEC. 14, T9S, R22E

14. PERMIT NO.

43-047-32375

15. ELEVATIONS (show whether DF, RY, GR, etc.)

4923' GR

12. COUNTY OR PARISH

UINTAH

13. STATE

UTAH

16. Check Appropriate Box to Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐

(Other)

WATER DISPOSAL METHODPULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐
☐
☐
☐
☒

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☐FRACTURE TREATMENT ☐SHOOTING OR ACIDIZING ☐(OTHER) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐
☐
☐
☐
☐

(NOTE: Report results of multiple completion on Well
Completion of Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Enron Oil & Gas Company requests approval to dispose of produced water from the subject well as follows:

- 1. Store in above ground tank.*
- 2. Transport by truck to Enron's NBU 21-20 SWD Plant.*

**Accepted by the State
of Utah Division of
Oil, Gas and Mining**

Date: 1-21-93By: [Signature]**RECEIVED****JAN 20 1993****DIVISION OF
OIL GAS & MINING**

18. I hereby certify that the foregoing is true and correct

SIGNED

(This space for Federal or State office use)

TITLE *Sr. Admin. Clerk*

DATE

01/18/93

APPROVED BY

Federal Approval of this

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY.

*See Instructions on Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

ENRON
Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

RECEIVED

JAN 22 1993

January 18, 1993
DIVISION OF
OIL GAS & MINING

Mr. Ed Forsman
Bureau Of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078

RE: FIRST SALES
CHAPITA WELLS 350-14N
LEASE: U-0282
SW/SE, SEC. 14, T9S, R22E
UINTAH COUNTY, UTAH

Mr. Forsman:

Please find attached a Sundry Notice of the first sales from the subject well.

If further information is required, please contact this office.

Sincerely,

for *Don Krause*
C.C. Parsons
District Manager

js

cc: UOG&M
D. Weaver
A.C. Morris
J. Tigner - EB 2043
Johnny Rodgers - 2127
File

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUNDRY NOTICE AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry to a different reservoir.
Use "APPLICATION FOR PERMIT --" for such proposals

SUBMIT IN TRIPLICATE

FORM APPROVED

Budget Bureau No. 1004-0135

Expires September 30, 1990

5. Lease Designation and Serial No.

U-0282

6. If Indian, Allottee or Tribe Name

7. If Unit or C.A., Agreement Designation

CHAPITA WELLS UNIT

8. Well Name and No.

CHAPITA WELLS 350-14N

9. API Well No.

43-047-32375

10. Field and Pool or Exploratory Area

CWU/WASATCH

11. COUNTY STATE

UINTAH UTAH

1. Type of Well

Oil

Gas

☐

WELL

☒

Well

☐

Other

2. Name of Operator

ENRON OIL & GAS COMPANY

3. Address and Telephone No.

P.O. BOX 250, BIG PINEY, WY 83113 (307) 276-3331

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

660' FSL - 1980' FEL (SW/SE)

SECTION 14, T9S, R22E

12. CHECK APPROPRIATE BOX(es) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

TYPE OF ACTION

☐

NOTICE OF INTENT

☒

SUBSEQUENT REPORT

☐

FINAL ABANDONMENT NOTICE

☐

ABANDONMENT

☐

RECOMPLETION

☐

PLUGGING BACK

☐

CASING REPAIR

☐

ALTERING CASING

☒

OTHER FIRST SALES

☐

CHANGE OF PLANS

☐

NEW CONSTRUCTION

☐

NON-ROUTINE FRACTURING

☐

WATER SHUT-OFF

☐

CONVERSION TO INJECTION

(Note: Report results of multiple completion on Well Completions
or Recompletion Report and Log Form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details and give pertinent dates, including estimated date of starting any proposed work if well is directionally drilled give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work).

FIRST SALES: 01/16/93, 1356 MCFD, 12/64TH CHOKE, TP 1640 PSIG, CP 1660 PSIG.

RECEIVED

JAN 22 1993

**DIVISION OF
OIL GAS & MINING**

14. I hereby certify that the foregoing is true and correct

SIGNED

Jennifer Schmid

TITLE

Engineering Clerk

DATE 01/18/92

(This space for Federal or State office use)

APPROVED BY

TITLE

DATE

CONDITIONS OF APPROVAL, IF ANY:

ENRON
Oil & Gas Company

P.O. Box 250 Big Piney, Wyoming 83113 (307) 276-3331

RECEIVED

JAN 29 1993

January 22, 1993

DIVISION C-
Oil & Gas Company

Mr. Ed Forsman
Bureau of Land Management
Vernal District
170 South 500 East
Vernal, Utah 84078


RE: COMPLETION REPORT
CHAPITA WELLS UNIT 350-14N
LEASE: U-0282
SW/SE, SEC. 14, T9S, R22E
UINTAH COUNTY, UTAH

Dear Mr. Forsman:

Please find attached a Completion Report describing the completion of the subject well.

If additional information is required, please contact this office.

Sincerely,


C.C. Parsons
District Manager

JLS/jls

cc: UOG&M
D. Weaver
A.C. Morris
J. Tigner - EB 2043
Vernal Office
File

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUBMIT IN DUPLICATE

See other in-
structions on
reverse sideForm approved.
Budget Bureau No. 42-R355.5.

WELL COMPLETION OR RECOMPLETION REPORT AND LOG *

| | | | |
|---|--|--|--|
| 1. TYPE OF WELL: OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> DRY <input type="checkbox"/> Other <input type="checkbox"/> | | 5. LEASE DESIGNATION AND SERIAL NO. U-0282 | |
| 2. TYPE OF COMPLETION: NEW WELL <input checked="" type="checkbox"/> WORK OVER <input type="checkbox"/> DEEP-EN <input type="checkbox"/> PLUG BACK <input type="checkbox"/> DIFF. RESVR. <input type="checkbox"/> Other <input type="checkbox"/> | | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME | |
| 3. NAME OF OPERATOR ENRON OIL & GAS COMPANY | | 7. UNIT AGREEMENT NAME CHAPITA WELLS UNIT | |
| 4. ADDRESS OF OPERATOR P.O. BOX 250 BIG PINEY, WYOMING 83113 | | 8. FARM OR LEASE NAME CHAPITA WELLS UNIT | |
| 4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements) At surface 660' FSL - 1980' FEL (SW/SE) At top prod. interval reported below SAME At total depth SAME | | 9. WELL NO. 350-14N | |
| 14. PERMIT NO. 43-047-32375 | | 10. FIELD AND POOL, OR WILDCAT CWU/WASATCH | |
| DATE ISSUED 09/29/92 | | 11. SEC., T., R., M., OR BLOCK AND SURVEY OR AREA SEC. 14, T9S, R22E | |
| 15. DATE SPUDDED 10/27/92 | | 12. COUNTY OR PARISH UINTAH | |
| 16. DATE T.D. REACHED 12/06/92 | | 13. STATE UTAH | |
| 17. DATE COMPL. (Ready to prod.) 01/16/93 | | 18. ELEVATIONS (OF. RES. RT. GR. ETC.) 4935' KB | |
| 19. ELEV. CASINGHEAD 4923 PREP. G.L. | | 20. TOTAL DEPTH, MD & TVD 6875' | |
| 21. PLUG. BACK T.D., MD & TVD 6640' KB | | 22. IF MULTIPLE COMPL. HOW MANY? ----- | |
| 23. INTERVALS DRILLED BY ROTARY | | 24. PRODUCING INTERVAL(S), OF THIS COMPLETION—TOP, BOTTOM, NAME (MD AND TVD) 5435-6584' (WASATCH) | |
| 25. WAS DIRECTIONAL SURVEY MADE NO | | 26. TYPE ELECTRIC AND OTHER LOGS RUN DLL/DSN/CDL/CALIPER, CBL/VDL/GR/CCL, CBL 1-20-93 | |
| 27. WAS WELL CORRED NO | | 28. CASING RECORD (Report all strings set in well) | |
| Casing Size | | Weight, lb./ft. | |
| Depth Set (MD) | | Hole Size | |
| Cementing Record | | Amount Pulled | |
| 9-5/8" | | 32.3# H-40 | |
| 232.57' KB | | 12-1/4" | |
| 125 sx. Class "G" | | None | |
| 4-1/2" | | 10.5# J-55 | |
| 6686.00' KB | | 7-7/8" | |
| 325 sx. HiLift | | None | |
| 660 sx. 50/50 Pozmix | | | |
| 29. LINER RECORD | | 30. TUBING RECORD | |
| Size | | Top (MD) | |
| Bottom (MD) | | Sacks Cement | |
| Screen (MD) | | Size | |
| Depth Set (MD) | | Packer Set (MD) | |
| 2-3/8" | | 6586.32' KB | |
| No | | | |
| 31. PERFORATION RECORD (Interval, size and number) | | 32. ACID, SHOT, FRACTURE, CEMENT SQUEEZE, ETC. | |
| BUCK CANYON: 5522-5500' -w/2 SPF | | DEPTH INTERVAL (MD) | |
| 6584-6575' - w/2 SPF | | 6584-75' | |
| CHAPITA WELLS: | | AMOUNT AND KIND OF MATERIAL USED | |
| 5734-5728' - w/4 SPF | | 8000 gals, 40# pad & 13,800 gals | |
| | | 35# borate, x-linked gel, w/ | |
| | | 82,100# 20/40 Ottawa sand. | |
| | | MP 4300 psig. (over) | |
| 33. PRODUCTION | | WELL STATUS (Producing or Shut-in) | |
| DATE FIRST PRODUCTION 01/16/93 | | Producing | |
| PRODUCTION METHOD (Flowing, gas lift, pumping—size and type of pump) Flowing | | | |
| DATE OF TEST 01/22/93 | | HOURS TESTED 24 HRS. | |
| CHOKER SIZE 12/64" | | PROD'N. FOR TEST PERIOD 0 BO | |
| OIL—BSL. 0 BO | | GAS—MCF. 1280 MCFD | |
| WATER—BSL. 3 BW | | GAS-OIL RATIO | |
| FLOW. TUBING PRESS. 1275 PSIG | | CASING PRESSURE 1400 PSIG | |
| CALCULATED 24-HOUR RATE 0 BO | | GAS—MCF. 1280 MCFD | |
| WATER—BSL. 3 BW | | OIL GRAVITY-API (CORR.) | |
| 34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.) Sold | | TEST WITNESSED BY Jay Orr | |
| 35. LIST OF ATTACHMENTS None | | | |
| 36. I hereby certify that the foregoing and attached information is complete and correct as determined from all available records | | | |
| SIGNED <u>Jimmy Schmidt</u> | | TITLE <u>Engineering Clerk</u> | |
| DATE <u>01/22/93</u> | | | |

*(See Instructions and Spaces for Additional Data on Reverse Side)

INSTRUCTIONS

General: This form is designed for submitting a complete and correct well completion report and log on all types of lands and leases to either a Federal agency or a State agency, or both, pursuant to applicable Federal and/or State laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office. See instructions on items 22 and 24, and 33, below regarding separate reports for separate completions. (formal-formation logs, etc.), formal-formation logs, sample and core analysis, all types electric, etc.). All attachments should be attached hereto, to the extent required by applicable Federal and/or State laws and regulations. Consult local State agency for details.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State agency for details.

Item 18: Indicate which elevation is used as reference (where not otherwise shown) for depth measurements given in other spaces on this form and in any attachments.

Items 22 and 24: If this well is completed for separate production from more than one interval zone (multiple completion), so state in item 22 and in item 24 show the producing interval, or intervals, top(s), bottom(s) and name(s) (if any) for only the interval reported in item 33. Submit a separate report (page) on this form, adequately identified, for each additional interval to be separately produced, showing the additional data pertinent to such interval.

Item 29: "Sacks Cement": Attached supplemental records for this well should show the details of any multiple stage cementing and the location of the cementing tool joint.

Item 33: Submit a separate completion report on this form for each interval to be separately produced. (See instruction for items 22 and 24 above.)

32.) 5734-5728' - No Stimulation
5522-5435' - 47,800 gals borate x-linked, gelled 2% KCl water & 207,120# 20/40 sand. MP 2728 psig.

| 37. SUMMARY OF POROUS ZONES: SHOW ALL IMPORTANT ZONES OF POROSITY AND CONTENTS THEREOF: CORED INTERVALS; AND ALL DRILL-STEM TESTS, INCLUDING DEPTH INTERVAL TESTED, CUSHION USED, TIME TOOL OPEN, FLOWING AND SHUT-IN PRESSURES, AND RECOVERIES | | 38. GEOLOGIC MARKERS | |
|---|------------------------------|----------------------|------------------|
| FORMATION | TOP DEPTH INTERVAL TESTED | MEAS. DEPTH | TRUE VERT. DEPTH |
| | | 4450' | +488' |
| GREEN RIVER | | 4674' | +264' |
| Base M Marker | | | |
| N. Limestone | | 4800' | +138' |
| WASATCH | | 5330' | -392' |
| Peter's Point | | 5890' | -952' |
| Chapita Wells | | | |
| Buck Canyon | | | |



Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

801-359-3940 (Fax)

801-538-5319 (TDD)

UTAH DIVISION OF OIL, GAS AND MINING FACSIMILE COVER SHEET

DATE: MARCH 12, 1997

FAX # (307) 276-3898

ATTN: BRENDA

COMPANY: ENRON OIL & GAS

FROM: LISHA CORDOVA

DEPARTMENT: OIL & GAS

NUMBER OF PAGES BEING SENT (INCLUDING THIS ONE): 5

If you do not receive all of the pages, or if they are illegible, please call (801) 538-

We are sending from a Sharp facsimile machine. Our telecopier number is (801) 359-3940.

MESSAGES:

SAME INFO FAXED TO CLAUDIA SILVER-HUFF/TRUST LANDS ADMIN. FOR REVIEW. SHE

WILL CALL ME BACK WITH UPDATE ASAP. I WILL LET YOU KNOW OUTCOME. IF YOU

WOULD LIKE TO TALK WITH HER PLEASE CALL (801)538-5100.

Important: This message is intended for the use of the individual or entity to which it is addressed and may contain information that is privileged, confidential and exempt from disclosure under applicable law. If the reader of this message is not the intended recipient, you are hereby notified that any dissemination, distribution, or copying of this communication is strictly prohibited. If you have received this communication in error, please notify us immediately by telephone and return this original message to us at the above address via regular postal service. Thank you.



State of Utah

DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

1594 West North Temple, Suite 1210

Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

March 12, 1997

Claudia Silver-Huff
School & Institutional Trust Lands Administration
675 East 500 South, Suite 500
Salt Lake City, Utah 84102

Re: Chapita Wells Unit - Wasatch PA "B-C-D-E" - Entities 4905
and 11455

Dear Claudia:

Enron Oil & Gas Co. has recently contacted the Division to request that wells currently listed under entity 11455 be changed to entity 4905 to make their reporting responsibilities easier and to eliminate the confusion regarding the double entity assignment for the Wasatch PA "B-C-D-E".

In January of 1993, all of these same wells were changed from entity 4905 to 11455 to accommodate and assist Trust Lands (formally "State Lands") with the collection of payor division order interest.

Please review the attached information and let me know if two separate entities are still necessary for the Wasatch PA "B-C-D-E".

Should you have any questions please call me at 538-5296.

Sincerely,

A handwritten signature in cursive script that reads "Lisha Cordova".

Lisha Cordova
Admin. Analyst

cc: Enron Oil & Gas Co.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
 1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114-5801

Page 11 of 12

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS:

PATTY E ROBINSON
 ENRON OIL & GAS CO
 PO BOX 250
 BIG PINEY WY 83113

UTAH ACCOUNT NUMBER: N0401REPORT PERIOD (MONTH/YEAR): 7 / 97AMENDED REPORT ☐ (Highlight Changes)

| Well Name | | | Producing Zone | Well Status | Days Oper | Production Volumes | | |
|---------------|--------|------------|-------------------|----------------|--------------|--------------------|----------|------------|
| API Number | Entity | Location | | | | OIL(BBL) | GAS(MCF) | WATER(BBL) |
| CWU 346-26N | | | | | | | | |
| 4304732368 | 11455 | 09S 22E 26 | WSTC | | | | | |
| CWU 343-15N | | | | | | | | |
| 4304732369 | 11455 | 09S 22E 15 | WSTC | | | | | |
| CWU 344-23N | | | | | | | | |
| 4304732370 | 11455 | 09S 22E 23 | WSTC | | | | | |
| CWU 341-21N | | | | | | | | |
| 4304732371 | 11455 | 09S 22E 21 | WSTC | | | | | |
| CWU 345-9N | | | | | | | | |
| 4304732372 | 11455 | 09S 22E 9 | WSTC | | | | | |
| CWU 348-23N | | | | | | | | |
| 4304732373 | 11455 | 09S 22E 23 | WSTC | | | | | |
| CWU 349-27N | | | | | | | | |
| 4304732374 | 11455 | 09S 22E 27 | WSTC | | | | | |
| CWU 350-14N | | | | | | | | |
| 4304732375 | 11455 | 09S 22E 14 | WSTC | | | | | |
| CWU 351-15N | | | | | | | | |
| 4304732390 | 11455 | 09S 22E 15 | WSTC | | | | | |
| CWU 337-9 | | | | | | | | |
| 4304732414 | 11455 | 09S 22E 9 | WSTC | | | | | |
| CWU 435-24N | | | | | | | | |
| 4304732639 | 11455 | 09S 22E 24 | WSTC | | | | | |
| CWU 433-28N | | | | | | | | |
| 4304732641 | 11455 | 09S 22E 28 | WSTC | | | | | |
| CWU 409-11N | | | | | | | | |
| 4304732643 | 11455 | 09S 22E 11 | WSTC | | | | | |
| TOTALS | | | | | | | | |

COMMENTS:

hereby certify that this report is true and complete to the best of my knowledge.

Date: _____

Name and Signature: _____

Telephone Number: _____

PHONE CONVERSATION DOCUMENTATION FORM

Route original/copy to:

☐ Well File _____

☐ Suspense
(Return Date) _____
(To - Initials) _____

☐ Other _____

(Location) Sec _____ Twp _____ Rng _____
(API No.) _____

1. Date of Phone Call: 8-15-97 Time: 11:30

2. DOGM Employee (name) L. CORDOVA (Initiated Call ~~XXX~~
Talked to:

Name RON CARLSON (Initiated Call ☐ - Phone No. (801) 538-5131
of (Company/Organization) TRUST LANDS (SITLA)

3. Topic of Conversation: CHAPITA WELLS UNIT-WASATCH "B-C-D-E" PA.
(ENTITY REVIEW 04905 AND 11455)

4. Highlights of Conversation: _____

A SECOND ENTITY NUMBER 11455 WAS ASSIGNED TO THE SAME PA 1/92 PER TRUST LANDS
(FORMERLY STATE LANDS) REQUEST. CAN WELLS BE COMBINED UNDER ONE ENTITY 04905
AS PER OPERATOR REQUEST & DOGM REVIEW? RON CARLSON WILL REVIEW & NOTIFY DOGM
OF OUTCOME.

*970819 - RON CARLSON SAYS OPERATOR "ENRON" IS REPORTING ALL DOE PAYMENTS, ETC.
UNDER ENTITY 04905; HE IS NOT SURE WHY A SECOND ENTITY OF 11455 WAS REQUESTED
BY THEM IN THE FIRST PLACE; MAY HAVE HAD SOMETHING TO DO WITH THEIR INTERNAL
SYSTEM; IT IS OK TO CHANGE ALL WELLS CURRENTLY UNDER ENTITY 11455 TO ENTITY
04905. ENRON NOTIFIED OF CHANGES TODAY 8-20-97.

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM - FORM 6

OPERATOR ENRON OIL & GAS

OPERATOR ACCT. NO. H 0401

ADDRESS _____

| ACTION CODE | CURRENT ENTITY NO. | NEW ENTITY NO. | API NUMBER | WELL NAME | WELL LOCATION | | | | | SPUD DATE | EFFECTIVE DATE |
|--|--------------------|----------------|-------------------------|--------------------|---------------|----|----|----|--------|-----------|----------------|
| | | | | | QQ | SC | TP | RG | COUNTY | | |
| C | 11455 | 04905 | 43-047-32375 | ***SEE ATTACHED*** | | | | | | | 8-1-97 |
| WELL 1 COMMENTS: *ENTITY 11455 ESTABLISHED 2/93 PER TRUST LANDS NO LONGER NECESSARY; ALL WELLS CURRENTLY UNDER 11455 ARE BEING CHANGED TO 04905 EFF 8-1-97. (CHAPITA WELLS UNIT - WSTC B-C-D-E PA). OPERATOR NOTIFIED. | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 2 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 3 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 4 COMMENTS: | | | | | | | | | | | |
| | | | | | | | | | | | |
| WELL 5 COMMENTS: | | | | | | | | | | | |

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/89)

L. CORDOVA (DOGM)

Signature

ADMIN. ANALYST

Title

8-20-97

Date

Phone No. () _____



EOG Resources, Inc.
1200 Smith Street
Houston, TX 77002

P.O. Box 4362
Houston, TX 77210-4362

October 6, 1999

VIA OVERNIGHT MAIL

Ms. Kristen Risbeck
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, Utah 84114-5801

RE: Blanket Oil & Gas Well Drilling Bond No. JT 1230
Merger and Name Change from Enron Oil & Gas Company
Into EOG Resources, Inc.

Dear Ms. Risbeck:

On August 30, 1999, EOG Resources, Inc. merged with and into Enron Oil & Gas Company and Enron Oil & Gas Company changed its name to EOG Resources, Inc. Enclosed are an originally certified copy of the Certificate of Ownership and Merger evidencing this merger and name change, a Rider for Bond No. JT 1230 changing the principal to EOG Resources, Inc. and a list of wells operated by Enron Oil & Gas Company in Utah. Please update your records accordingly.


If you have any questions or need any additional information, please contact me at (713) 853-5195.

Sincerely,

Debbie Hamre

Enclosures

cc: Theresa Wysocki
Toni Miller, Denver Division
Bill Aven



ENRON OIL & GAS COMPANY
CERTIFICATE OF NAME CHANGE
TO EOG RESOURCES, INC.

I, the undersigned, Vickie L. Graham, Assistant Secretary of EOG Resources, Inc., a corporation duly organized and existing under and by virtue of the laws of the State of Delaware and formerly known as Enron Oil & Gas Company, hereby certify that:

- (1) as Assistant Secretary I am authorized to execute this certificate on behalf of the Corporation;
- (2) attached is a true and correct copy of a Certificate of Ownership and Merger merging EOG Resources, Inc. into Enron Oil & Gas Company, and changing the corporate name of Enron Oil & Gas Company to EOG Resources, Inc., including a copy of the certificate of the Secretary of State of Delaware, the state of incorporation; said merger and name change being effective as of August 30, 1999.

IN WITNESS HEREOF, I have hereunto set my hand as Assistant Secretary and affixed the corporate seal of said Corporation this 4th day of October, 1999.


CORPORATE SEAL

Vickie L. Graham
Vickie L. Graham
Assistant Secretary

STATE OF TEXAS

COUNTY OF HARRIS

This instrument was acknowledged before me this 4th day of October, 1999 by Vickie L. Graham, as Assistant Secretary of EOG Resources, Inc., a Delaware corporation, on behalf of said corporation. Witness my hand and official seal.



Ann S. Byers
Notary Public in and for
The State of Texas

Office of the Secretary of State

I, EDWARD J. FREEL, SECRETARY OF STATE OF THE STATE OF DELAWARE, DO HEREBY CERTIFY THE ATTACHED IS A TRUE AND CORRECT COPY OF THE CERTIFICATE OF MERGER, WHICH MERGES:

"EOG RESOURCES, INC.", A DELAWARE CORPORATION,
WITH AND INTO "ENRON OIL & GAS COMPANY" UNDER THE NAME OF
"EOG RESOURCES, INC.", A CORPORATION ORGANIZED AND EXISTING
UNDER THE LAWS OF THE STATE OF DELAWARE, AS RECEIVED AND FILED
IN THIS OFFICE THE THIRTIETH DAY OF AUGUST, A.D. 1999, AT 4:30
O'CLOCK P.M.



Edward J. Freel, Secretary of State

2064000 8100M

991371085

AUTHENTICATION: 9955549

DATE: 09-03-99

8-30-99

**CERTIFICATE OF OWNERSHIP
AND MERGER**

MERGING

EOG RESOURCES, INC.
a Delaware corporation

INTO

ENRON OIL & GAS COMPANY
a Delaware corporation

(Pursuant to Section 253 of the General Corporation
Law of the State of Delaware)

Enron Oil & Gas Company, a corporation duly organized and existing under and by virtue of the General Corporation Law of the State of Delaware, does hereby certify:

FIRST: That Enron Oil & Gas Company (the "Company") and EOG Resources, Inc. ("EOG") are corporations duly organized and existing under and by virtue of the General Corporation Law of the State of Delaware.

SECOND: That the Company owns all of the issued and outstanding shares of the capital stock of EOG.

THIRD: That the board of directors of the Company adopted the following resolutions by unanimous written consent dated August 25, 1999, and that such resolutions have not been rescinded and are in full force and effect on the date hereof:

"WHEREAS, EOG Resources, Inc., a Delaware corporation ("EOG"), is a wholly owned subsidiary of the Company;

WHEREAS, the board of directors of the Company deems it advisable and in the best interest of the Company to merge EOG with and into the Company, with the Company being the surviving corporation;

NOW, THEREFORE, BE IT RESOLVED, that EOG be merged with and into the Company pursuant to Section 253 of the General Corporation Law of the State of Delaware, and that the Company succeed to and possess all the rights and assets of EOG and be subject to all of the liabilities and obligations of EOG;

RESOLVED, that the Company change its corporate name by changing Article First of the Certificate of Incorporation of the Company to read in its entirety as follows:

"First: The name of the Corporation is EOG Resources, Inc."

RESOLVED, that each share of common stock, \$1.00 par value per share, of EOG issued and outstanding immediately prior to the effective date of the merger shall, upon the effective date and by virtue of the merger, be canceled without payment therefor;

RESOLVED, that the merger shall become effective on the date the Company files a Certificate of Ownership and Merger with respect to such merger with the Secretary of State of the State of Delaware;


RESOLVED, that the appropriate officers of the Company are hereby authorized and empowered to file the necessary documents with the Secretary of State of the State of Delaware, to incur the necessary expenses therefor and to take, or cause to be taken, all such further action and to execute and deliver or cause to be executed and delivered, in the name of and on behalf of the Company, all such further instruments and documents as any such officer may deem to be necessary or advisable in order to effect the purpose and intent of the foregoing resolutions and to be in the best interests of the Company (as conclusively evidenced by the taking of such action or the execution and delivery of such instruments and documents, as the case may be, by or under the direction of any such officer);

RESOLVED, that the prior actions of the officers and directors of the Company in undertaking to carry out the transactions contemplated by the foregoing resolutions be, and the same hereby are, in all respects, approved, adopted, ratified and confirmed."

IT WITNESS WHEREOF, the Company has caused this Certificate to be signed by its duly authorized officer this 26th day of August, 1999.

ENRON OIL & GAS COMPANY

By:


Walter C. Wilson
Senior Vice President and
Chief Financial Officer

BKJ



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, UT 84145-0155

In Reply Refer To:
3100
SL-065342 et al
(UT-932)

OCT 18 1999

NOTICE

EOG Resources, Inc.
Attn: Debbie Hamre
P.O. Box 4362
Houston, TX 77210-4362

Oil and Gas Leases

Merger Recognized Name Change Recognized

Acceptable evidence has been received in this office concerning the merger of EOG Resources, Inc. with and into Enron Oil & Gas Company with Enron Oil & Gas Company subsequently changing its name to EOG Resources, Inc.

For our purposes, the merger and name change are recognized effective September 3, 1999, the date the Secretary of State of the State of Delaware recognized the merger and name change.


The oil and gas lease files identified on the enclosed exhibit have been noted as to the merger/name change. The exhibit is the list supplied by EOG Resources, Inc. We have not adjudicated the case files to determine if the entity affected by the merger/name change holds an interest in the leases identified, nor have we attempted to identify leases where the entity is the operator on the ground maintaining no vested record title or operating rights interest. We are notifying the Minerals Management Service and all applicable BLM offices of the merger/name change by a copy of this notice. If additional documentation for a change of operator is required by our Field Offices, you will be contacted by them.

Due to the name change, the name of the principal/obligor on the bond is required to be changed from Enron Oil & Gas Company to EOG Resources, Inc. on Nationwide Surety Bond No. JP 0923 (BLM Bond No. NM 2308). You may accomplish this name change either by consent of the surety on the original bond or by a rider to the original bond. Otherwise, a replacement bond with the new name may be furnished to the New Mexico State Office of the Bureau of Land Management.

Robert Lopez

Robert Lopez
Chief, Branch of
Minerals Adjudication

Enclosure:
Exhibit of Leases



STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

01/18/2000

1594 West North Temple, Suite 1210, PO Box 145801, Salt Lake City, UT 84114-5801

MONTHLY OIL AND GAS PRODUCTION REPORT

OPERATOR NAME AND ADDRESS

PATTY E ROBINSON
ENRON OIL & GAS CO
PO BOX 250
BIG PINEY, WY 83113

UTAH ACCOUNT NUMBER: N0401REPORT PERIOD (MONTH/YEAR): 12 / 1999AMENDED REPORT ☐ (Highlight Changes)

| WELL NAME | | | Producing Zone | Well Status | Well Type | Days Oper | Production Volumes | | |
|--|--------|----------|-------------------|----------------|--------------|--------------|--------------------|----------------------|-----------------|
| API Number | Entity | Location | | | | | OIL (BBL) | GAS (MCF) | WATER (BBL) |
| CWU 346-26N 4304732368 04905 09S 22E 26 | | | WSTC | | GW | | U-0285A | Capita wells unit | approx 10.20.99 |
| CWU 343-15N 4304732369 04905 09S 22E 15 | | | WSTC | | GW | | U-0283A | 11 | 11 |
| CWU 344-23N 4304732370 04905 09S 22E 23 | | | WSTC | | GW | | U-0282 | 11 | 11 |
| CWU 341-21N 4304732371 04905 09S 22E 21 | | | WSTC | | GW | | U-0284A | 11 | 11 |
| CWU 345-9N 4304732372 04905 09S 22E 09 | | | WSTC | | GW | | U-0283A | 11 | 11 |
| J 348-23N 4304732373 04905 09S 22E 23 | | | WSTC | | GW | | U-0282 | 11 | 11 |
| CWU 349-27N 4304732374 04905 09S 22E 27 | | | WSTC | | GW | | U-0285A | 11 | 11 |
| CWU 350-14N 4304732375 04905 09S 22E 14 | | | WSTC | | GW | | U-0282 | 11 | 11 |
| CWU 351-15N 4304732390 04905 09S 22E 15 | | | WSTC | | GW | | U-0283A | 11 | 11 |
| CWU 337-9 4304732414 04905 09S 22E 09 | | | WSTC | | GW | | FEE | 11 | 11 |
| CWU 340-26 4304732419 04905 09S 22E 26 | | | WSTC | | GW | | U-0285A | 11 | 11 |
| CWU 332-10 4304732431 04905 09S 22E 10 | | | WSTC | | GW | | U-0281 | 11 | 11 |
| CWU 360-26N 4304732432 04905 09S 22E 26 | | | WSTC | | GW | | U-0285A | 11 | 11 |

TOTALS

| | | |
|--|--|--|
| | | |
|--|--|--|

COMMENTS :

I hereby certify that this report is true and complete to the best of my knowledge.

Date: _____

Name and Signature: _____

Telephone Number: _____



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Kathleen Clarke
Executive Director

Lowell P. Braxton
Division Director

1594 West North Temple, Suite 1210

PO Box 145801

Salt Lake City, Utah 84114-5801

801-538-5340

801-359-3940 (Fax)

801-538-7223 (TDD)

February 1, 2000

Enron Oil & Gas Company
P.O. Box 250
Big Piney, Wyoming 83113

Re: Notification of Sale or Transfer of Fee Lease Interest

The Division has received notification of a merger from Enron Oil & Gas Company to EOG Resources Inc. for the following well(s) which are located on a fee lease:

| <u>Well Name</u> | <u>Sec.-T.-R.</u> | <u>API Number</u> |
|-------------------|-------------------|-------------------|
| Stagecoach 18-17 | 17-09S-22E | 43-047-30611 |
| CWU 228-09 | 09-09S-22E | 43-047-31317 |
| CWU 337-09 | 09-09S-22E | 43-047-32414 |
| CWU 408-9N | 09-09S-22E | 43-047-33043 |
| CWU 536-9F | 09-09S-22E | 43-047-33143 |
| North Chapita 2-5 | 05-09S-22E | 43-047-33211 |
| CWU 535-9F | 09-09S-22E | 43-047-33275 |

Utah Administrative Rule R649-2-10 states; the owner of a lease shall provide notification to any person with an interest in such lease, when all or part of that interest in the lease is sold or transferred.

This letter is written to advise Enron Oil & Gas Company of its responsibility to notify all individuals with an interest in this lease (royalty interest and working interest) of the change of operator. Please provide written documentation of this notification to:

Utah Royalty Owners Association
Box 1292
Roosevelt, Utah 84066

Page 2
Enron Oil & Gas Company
Notification of Sale
February 1, 2000

Your assistance in this matter is appreciated.

Sincerely,

A handwritten signature in black ink that reads "Kristen D. Risbeck". The signature is written in a cursive style with a large, stylized "K" and "R".

Kristen D. Risbeck

cc: EOG Resources Inc.
Utah Royalty Owners Association, Martin Brotherson
John R. Baza, Associate Director
Operator File(s)



EOG Resources, Inc.
1200 Smith Street
Houston, TX 77002

P.O. Box 4362
Houston, TX 77210-4362

SENT VIA FAX
(801)359-3940

March 10, 2000

Ms. Kristen Risbeck
State of Utah
Division of Oil, Gas and Mining
1594 West North Temple, Suite 1210
P. O. Box 145801
Salt Lake City, UT 84114-5801

RE: Merger and Name Change from Enron Oil & Gas Company
Into EOG Resources, Inc.

Dear Ms. Risbeck:

On August 30, 1999, EOG Resources, Inc. merged with and into Enron Oil & Gas Company and Enron Oil & Gas Company changed its name to EOG Resources, Inc. An originally certified copy of the Certificate of Ownership and Merger evidencing this merger and name change was previously sent to you. As we discussed today, there are two wells, the CWU 590-16F, NWNW-16-T9S-R22E, 430473337200 and the CWU 596-9F, SWSE-9-T9S-R22E, 430473337400 that should have been included on the original well list we mailed October 6, 1999, but they were inadvertently left off.

Please change your records to reflect these two additional wells as operated by EOG Resources, Inc. If you have any questions or need any additional information, please contact me at the (713) 651-6714.

Sincerely,


Debbie Hamre

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|----------------------|----------------|--------------|
| BRENNAN BOTTOMS 1-15 | U-14639 | 430473101800 |
| COTTONTAIL FED 1-18 | U-0575 | 430473189900 |
| COTTONWOOD FED 1-20 | U-0575 | 430473187500 |
| CWU 1-04 | U-15726 | 430473066000 |
| CWU 1-05 WASATCH | U-15727 | 430473066100 |
| CWU 5-22 | U-0284A | 430471505100 |
| CWU 7-10 | U-0281 | 430471505300 |
| CWU 11-15 | U-0283A | 430471505600 |
| CWU 13-13 | U-0282 | 430471505800 |
| CWU 15-11 | U-0281 | 430471506000 |
| CWU 16-14 | U-0282 | 430471506100 |
| CWU 17-25 | U-0285A | 430471506200 |
| CWU 20-28 | U-0285A | 430471506500 |
| CWU 21-23 | U-0282 | 430471506600 |
| CWU 22-09 | U-0283A | 430471506700 |
| CWU 24-02 | ML-3077 | 430471506800 |
| CWU 30-22 | U-0284A | 430473022900 |
| CWU 31-14 | U-0282 | 430473023200 |
| CWU 32-21 | U-0284A | 430473023300 |
| CWU 33-16 | ML-3078 | 430473023400 |
| CWU 34-28 | SL-D65296 | 430473023500 |
| CWU 35-15 | U-0283A | 430473023600 |
| CWU 36-26 | U-0285A | 430473026300 |
| CWU 37-11 | U-0281 | 430473026400 |
| CWU 38-09 | U-0283A | 430473026500 |
| CWU 39-16 | ML-3078 | 430473026800 |
| CWU 40-27 | U-0344A | 430473028700 |
| CWU 42-13 | U-0282 | 430473028900 |
| CWU 43-11 | U-0281 | 430473029000 |
| CWU 44-10 | U-0281 | 430473029100 |
| CWU 45-25 | U-010956 | 430473061200 |
| CWU 47-30 | U-0337 | 430473061400 |
| CWU 48-19 | U-0337 | 430473061500 |
| CWU 49-25 | U-0285A | 430473070200 |
| CWU 52-33 | U-0336 | 430473071200 |
| CWU 58-19 | U-0337 | 430473082700 |
| CWU 217-23 | U-0282 | 430473115700 |
| CWU 220-10 | U-0281 | 430473115400 |
| CWU 224-10 | U-0281 | 430473121800 |
| CWU 225-02 | ML-3077 | 430473130500 |
| CWU 226-03 | U-0281 | 430473131200 |
| CWU 227-03 | U-0281 | 430473131300 |
| CWU 228-09 | FEE | 430473131700 |
| CWU 229-12 | U-0282 | 430473131500 |
| CWU 231-14 | U-0282 | 430473131800 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|-----------------|----------------|--------------|
| CWU 232-15 | U-0283A | 003693000001 |
| CWU 233-15 | U-0283A | 003694000001 |
| CWU 234-23 | U-0282 | 003695000001 |
| CWU 236-13 BC | U-0282 | 003697000001 |
| CWU 236-13 PP | | 003697000002 |
| CWU 237-22 | U-0284 | 003698000001 |
| CWU 238-16 | ML-3078 | 003699000001 |
| CWU 239-09 | U-0283A | 003700000001 |
| CWU 240-16 | ML-3078 | 003702000001 |
| CWU 241-16 | ML-3078 | 003703000001 |
| CWU 244-25A CH | U-0285A | 003707000002 |
| CWU 244-25A ISL | | 003707000001 |
| CWU 301-26 | U-010956 | 019747000001 |
| CWU 302-2F | ML-3077 | 020089000001 |
| CWU 303-22 | U-0284A | 019748000001 |
| CWU 304-13 | U-0282 | 019749000001 |
| CWU 306-27 | U-0285A | 021166000001 |
| CWU 307-28 | U-0285A | 021167000001 |
| CWU 308-21 | U-0284A | 021168000001 |
| CWU 310-9 | U-0283A | 024129000001 |
| CWU 311-26 | U-0285A | 021169000001 |
| CWU 312-23 | U-0282 | 020022000001 |
| CWU 315-11F | U-0281 | 032567000001 |
| CWU 319-14 | U-0282 | 020023000001 |
| CWU 320-11X | U-0281 | 024130000001 |
| CWU 321-26 | U-0285A | 020025000001 |
| CWU 323-22 | U-0284A | 020024000001 |
| CWU 324-22 | U-0284A | 021172000001 |
| CWU 325-24N | U-0282 | 031378000001 |
| CWU 326-24 | U-0282 | 021628000001 |
| CWU 327-23 | U-0282 | 021629000001 |
| CWU 328-24F | U-0282 | 032254000001 |
| CWU 332-10 | U-0281 | 024131000001 |
| CWU 334-02 | ML-3077 | 021630000001 |
| CWU 337-9N | FEE | 021631000001 |
| CWU 339-25 | U-010956 | 021173000001 |
| CWU 340-26N | U-0285A | 024133000001 |
| CWU 341-21N | U-0284A | 022029000001 |
| CWU 342-22 | U-0284A | 021198000001 |
| CWU 343-15N | U-0283A | 022030000001 |
| CWU 344-23N | U-0282 | 022031000001 |
| CWU 345-9N | U-0283A | 022032000001 |
| CWU 346-26N | U-0285A | 022033000001 |
| CWU 347-26N | U-010956 | 022034000001 |
| CWU 348-23N | U-0282 | 022035000001 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|-------------|-----------------------|---------------------------|
| CWU 349-27N | U-0285A | 022036000001 430473237400 |
| CWU 350-14N | U-0282 | 022037000001 430473237500 |
| CWU 351-15N | U-0283A | 022038000001 430473239000 |
| CWU 352-16 | ML-31603 | 032569000001 430473333000 |
| CWU 353-15F | U-0283A | 025923000001 430473255500 |
| CWU 355-13N | U-0282 | 025926000001 430473264400 |
| CWU 358-23F | U-0282 | 025924000001 430473254800 |
| CWU 359-27N | U-0285A | 024135000001 430473243300 |
| CWU 360-26N | U-0285A | 024136000001 430473243200 |
| CWU 364-15 | U-0283A | 024138000001 430473243600 |
| CWU 401-28F | U-0285A | 031398000001 430473313300 |
| CWU 403-3N | U-0281 | 025124000001 430473251000 |
| CWU 404-10N | U-0281 | 025125000001 430473251100 |
| CWU 407-16N | ML-3078 | 032570000001 430473334700 |
| CWU 408-09N | FEE | 030439000001 430473304300 |
| CWU 409-11N | U-0281 | 025927000001 490353264300 |
| CWU 410-02N | ML-3077 | 030389000001 430473289300 |
| CWU 411-10N | U-0281 | 025126000001 430473249600 |
| CWU 416-24N | SL-071756 | 025127000001 430473250100 |
| CWU 429-22N | U-0284A | 025129000001 430473248400 |
| CWU 430-22F | U-0284A | 025130000001 430473248500 |
| CWU 431-23F | U-0282 | 025131000001 430473248600 |
| CWU 432-12N | U-0281 | 025123000001 430473252300 |
| CWU 433-28N | U-0285A | 002592900001 4304732641 |
| CWU 434-27N | *43-047-32789 U-0285A | 025930000001 430473264000 |
| CWU 435-24N | U-0282 | 025931000001 430473263900 |
| CWU 439-11N | U-0281 | 025932000001 430473285100 |
| CWU 440-14F | U-0282 | 025925000001 430473256200 |
| CWU 441-11F | U-0281 | 032571000001 430473334800 |
| CWU 442-11F | U-0281 | 030577000001 430473295100 |
| CWU 443-11F | U-0281 | 027627000001 430473282300 |
| CWU 448-10F | U-0281 | 030440000001 430473304400 |
| CWU 449-10F | U-0281 | 030666000001 430473304500 |
| CWU 451-14F | U-0282 | 027628000001 430473282400 |
| CWU 454-14F | U-0282 | 030441000001 430473291400 |
| CWU 457-15N | U-0283A | 030667000001 430473295200 |
| CWU 458-15F | U-0283A | 030668000001 430473295400 |
| CWU 460-16F | ML-3078 | 032572000001 430473334900 |
| CWU 462-24F | SL-071756 | 032255000001 430473331400 |
| CWU 463-23F | U-0282 | 027629000001 430473284100 |
| CWU 464-23F | U-0282 | 032573000001 430473331500 |
| CWU 465-23 | U-0282 | 030669000001 430473292500 |
| CWU 467-22F | U-0284A | 030390000001 430473289500 |
| CWU 469-22E | U-0284A | 027630000001 430473282500 |
| CWU 471-21F | U-0284A | 031399000001 430473314100 |

LA in ERROR

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|-------------|----------------|--------------|
| CWU 474-21F | U-0284A | 032574000001 |
| CWU 477-27F | U-0285A | 030391000001 |
| CWU 479-26F | U-0285A | 027631000001 |
| CWU 480-26F | U-0285A | 030388000001 |
| CWU 482-09F | U-0283A | 030392000001 |
| CWU 483-15F | U-0283A | 030665000001 |
| CWU 485-26F | U-0285A | 030670000001 |
| CWU 486-2F | ML-3077 | 030576000001 |
| CWU 487-09F | U-0283A | 030617000001 |
| CWU 488-13F | U-0282 | 030570000001 |
| CWU 490-16N | ML-3078 | 030615000001 |
| CWU 491-16N | ML-3078 | 030618000001 |
| CWU 492-16F | ML-3078 | 030616000001 |
| CWU 494-22F | U-0284A | 030444000001 |
| CWU 495-25N | U-0285A | 030673000001 |
| CWU 496-21E | U-0284A | 030614000001 |
| CWU 497-24F | U-0282 | 030674000001 |
| CWU 498-25E | U-010956 | 030575000001 |
| CWU 499-24F | U-0282 | 030672000001 |
| CWU 505-28F | U-023998 | 031400000001 |
| CWU 506-27F | U-0285A | 031401000001 |
| CWU 507-26F | U-010956 | 032444000001 |
| CWU 511-24F | U-0282 | 031379000001 |
| CWU 514-23F | U-0282 | 031380000001 |
| CWU 516-21F | U-0284A | 031382000001 |
| CWU 517-16F | ML-3078 | 032257000001 |
| CWU 518-16F | ML-3078 | 031402000001 |
| CWU 520-15F | U-0283A | 031381000001 |
| CWU 521-15F | U-0283A | 032258000001 |
| CWU 522-15F | U-0283A | 032242000001 |
| CWU 523-14F | U-0282 | 032259000001 |
| CWU 524-13F | U-0282 | 031403000001 |
| CWU 531-11F | U-0281 | 032260000001 |
| CWU 532-10F | U-0281 | 031407000001 |
| CWU 534-9F | U-0283A | 031408000001 |
| CWU 535-9F | FEE | 032220000001 |
| CWU 536-09F | FEE | 031409000001 |
| CWU 538-3N | U-0281 | 031410000001 |
| CWU 542-3 | U-0281 | 032221000001 |
| CWU 543-3 | U-0281 | 032222000001 |
| CWU 544-02F | ML-3077 | 032576000001 |
| CWU 547-2F | ML-3077 | 031412000001 |
| CWU 549-19F | U-0337 | 031383000001 |
| CWU 550-30N | U-0337 | 031384000001 |
| CWU 555-10F | U-0281 | 031385000001 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|------------------------|----------------|--------------|
| CWU 556-11F | U-0281 | 031414000001 |
| CWU 558-14F | U-0282 | 031386000001 |
| CWU 559-14F | U-0282 | 031387000001 |
| CWU 560-14F | U-0282 | 031416000001 |
| CWU 561-14F | U-0282 | 031417000001 |
| CWU 563-27F | U-0285A | 031419000001 |
| CWU 564-16F | ML-3078 | 031388000001 |
| CWU 565-28F | U-0285A | 031245000001 |
| CWU 566-22F | U-0284A | 031420000001 |
| CWU 570-02F | ML-3077 | 031746000001 |
| CWU 571-9F | U-0283A | 031747000001 |
| CWU 572-10F | U-0281 | 031748000001 |
| CWU 573-11F | U-0281 | 031749000001 |
| CWU 574-12N | U-0281 | 031750000001 |
| CWU 575-13F | U-0282 | 031751000001 |
| CWU 576-14F | U-0283 | 031752000001 |
| CWU 577-22F | U-0284A | 031753000001 |
| CWU 578-22F | U-0284A | 031754000001 |
| CWU 579-23F | U-0282 | 031755000001 |
| CWU 580-23F | U-0282 | 031756000001 |
| CWU 582-1N | U-01458 | 031758000001 |
| CWU 584-13F | U-0282 | 032261000001 |
| CWU 585-2 | ML-3077 | 032223000001 |
| CWU 586-4 | U-0283A | 032224000001 |
| CWU 589-28 | U-0285A | 032262000001 |
| CWU 591-23F | U-0282 | 032577000001 |
| CWU 592-11F | U-0281 | 032578000001 |
| CWU 593-11F | U-0281 | 032579000001 |
| DC 1-11 GR | U-27042 | 003747000001 |
| DC 2-10 GR | U-27042 | 003758000001 |
| DC 4-17 GR | U-38400 | 003780000001 |
| DC 60-29 | U-24230 | 003804000001 |
| DC 61-29 | U-24230 | 003805000001 |
| * HARLEY GOVT #1 | U-3405 | 009856000001 |
| HOME FEDERAL #1-34 | U-3405 | 006503000001 |
| HOME FEDERAL #1-34 WAS | — | 006503000002 |
| LTL PAP 1-26 B5 | U-43560 | 010439000001 |
| LTL PAP 1-26 RED | — | 010439000002 |
| N CHAPITA 2-5 | file | 031873000001 |
| NATURAL COTTON 11-20 | U-0575 | 023868000001 |
| NATURAL COTTON 12-17 | U-0575 | 025208000001 |
| NATURAL COTTON 13-20 | U-0575 | 023863000001 |
| NATURAL COTTON 14-08 | U-0575 | 023867000001 |
| NATURAL COTTON 23-18 | U-0581 | 023866000001 |
| NATURAL COTTON 23-28 | U-0576 | 023864000001 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|----------------------|-----------------------|--------------|
| NATURAL COTTON 34-21 | U-1576 023865000001 | 430473242600 |
| NATURAL COTTON 43-16 | ML-3282 025207000001 | 430473046800 |
| NBU 1-07B | 004478000001 | 430473026100 |
| NBU 2-15B | 004489000001 | 430473026200 |
| NBU 3-02B | 004524000001 | 430473026700 |
| NBU 4-35B | 004538000001 | 430473027300 |
| NBU 5-36B | 004550000001 | 430473027200 |
| NBU 7-09B | 004573000001 | 430473027800 |
| NBU 8-20B | 004576000001 | 430473027500 |
| NBU 10-29B | 004479000001 | 430473027400 |
| NBU 11-14B | U-0577A 004480000002 | 430473029200 |
| NBU 11-14B WAS | — | 430473029200 |
| NBU 12-23B M4 | U-0577A 004481000002 | 430473030800 |
| NBU 13-08B | 004482000001 | 430473029400 |
| NBU 14-30 | U-0581 004483000001 | 430473029500 |
| NBU 15-29B | 004484000001 | 430473029600 |
| NBU 16-06B | 004485000001 | 430473031600 |
| NBU 17-18B | 004486000001 | 430473031700 |
| NBU 19-21B | 004488000001 | 430473032800 |
| NBU 20-01B | 004490000001 | 430473031900 |
| NBU 21-20B WDW | 004497000001 | 430473035900 |
| NBU 25-20B | 004516000001 | 430473036300 |
| NBU 26-13B | 004517000001 | 430473036400 |
| NBU 27-01B | U-02270A 004518000002 | 430473038100 |
| NBU 28-04B | 004521000001 | 430473036700 |
| NBU 29-05B | 004523000001 | 430473036800 |
| NBU 30-18 | 004526000001 | 430473038000 |
| NBU 31-12B BC | 004528000002 | 430473038500 |
| NBU 31-12B ISL | — 004528000001 | 430473038500 |
| NBU 33-17B | 004531000001 | 430473039600 |
| NBU 34-17B | 000350000001 | 430473040400 |
| NBU 35-08B | 004533000001 | 430473039700 |
| NBU 36-07B | 004534000001 | 430473039900 |
| NBU 37-13B | U-0579 004535000001 | 430473040000 |
| NBU 38-22B | U-0577A 004536000001 | 430473040100 |
| NBU 48-29B | 004547000001 | 430473054200 |
| NBU 48-29B | — 004547000002 | 430473054200 |
| NBU 49-12B | 004548000001 | 430473047000 |
| NBU 52-01B | 004553000001 | 430473047300 |
| NBU 53-03B | 004555000001 | 430473047400 |
| NBU 54-02B | 004556000001 | 430473047500 |
| NBU 55-10B | 004557000001 | 430473046500 |
| NBU 57-12B | 004559000001 | 430473046300 |
| NBU 58-23B | 004560000001 | 430473046200 |
| NBU 62-35B | 004565000001 | 430473047700 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|-------------|----------------|--------------|
| NBU 63-12B | 004566000001 | 430473046600 |
| NBU 70-34B | 004574000001 | 430473057700 |
| NBU 71-26B | 004575000001 | 430473057800 |
| NBU 202-03 | 004493000001 | 430473115000 |
| NBU 205-08 | 004494000001 | 430473123800 |
| NBU 206-09 | 004495000001 | 430473116500 |
| NBU 207-04 | 004496000001 | 430473117700 |
| NBU 210-24 | 004498000001 | 430473115300 |
| NBU 211-20 | 004499000001 | 430473115600 |
| NBU 212-19 | 004500000001 | 430473126700 |
| NBU 213-36 | 004501000001 | 430473126800 |
| NBU 217-02 | 004505000001 | 430473128200 |
| NBU 218-17 | 004506000001 | 430473131000 |
| NBU 219-24 | 004507000001 | 430473130800 |
| NBU 301-24E | 020165000001 | 430473213100 |
| NBU 302-9E | 019750000001 | 430473201000 |
| NBU 304-18E | 020166000001 | 430473213000 |
| NBU 305-07E | 020167000001 | 430473213500 |
| NBU 306-18E | 021473000001 | 430473228200 |
| NBU 307-6E | 019751000001 | 430473201400 |
| NBU 308-20E | 021203000001 | 430473220200 |
| NBU 309-20E | 021295000001 | 430473228300 |
| NBU 311-23E | 021205000001 | 430473220300 |
| NBU 313-29E | 021832000001 | 430473237800 |
| NBU 314-03E | 021404000001 | 430473227100 |
| NBU 316-17E | 021935000001 | 430473238100 |
| NBU 317-12E | 021938000001 | 430473236200 |
| NBU 318-36E | 021204000001 | 430473220400 |
| NBU 321-10E | 021943000001 | 430473237900 |
| NBU 322-15E | 031312000001 | 430473313900 |
| NBU 325-8E | 021940000001 | 430473237600 |
| NBU 328-13E | 021944000001 | 430473238600 |
| NBU 329-29E | 021532000001 | 430473222900 |
| NBU 331-35E | 020174000001 | 430473214700 |
| NBU 332-08E | 020175000001 | 430473214800 |
| NBU 333-2E | 021405000001 | 430473251800 |
| NBU 335-23E | 021406000001 | 430473226500 |
| NBU 336-24E | 021407000001 | 430473226400 |
| NBU 339-19E | 021533000001 | 430473228100 |
| NBU 340-20E | 021408000001 | 430474232700 |
| NBU 341-29E | 022179000001 | 430473305500 |
| NBU 342-35E | 021206000001 | 430473221200 |
| NBU 343-36E | 021207000001 | 430473220500 |
| NBU 349-07E | 021534000001 | 430473232600 |
| NBU 352-10E | 021937000001 | 430473251900 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | EOG PROPERTY # | API # |
|--------------------|---------------------------------|--------------|
| NBU 356-29E | 021834000001 | 430473238300 |
| NBU 358-1E | 021942000001 | 430473238800 |
| NBU 360-13E | 021945000001 | 430473238700 |
| NBU 382-18E | 031002000001 | 430473306400 |
| NBU 386-24E | 031005000001 | 430473305600 |
| NBU 388-19E | 031134000001 | 430473305700 |
| NBU 389-29E | 031344000001 | 430473304900 |
| NBU 390-4E | 031316000001 | 430473283500 |
| NBU 391-05E | 031007000001 | 430473298800 |
| NBU 393-13E | 031008000001 | 430473307100 |
| NBU 394-13E | 031009000001 | 430473307200 |
| NBU 400-11E | 025576000001 | 430473254400 |
| NBU 431-09E | 031135000001 | 430473306900 |
| NBU 481-03E | 031136000001 | 430473306300 |
| NBU 483-19E | 031137000001 | 430473306500 |
| NBU 489-07E | 031329000001 | 4304733121 |
| NBU 490-30E | <i>Apd. U-0581</i> 031330000001 | 430473313500 |
| NBU 497-1E | 031337000001 | 430473312300 |
| NBU 506-23E | 031342000001 | 430473314000 |
| NBU 508-8E | 031300000001 | 430473312400 |
| NBU STATE 1-32G | <i>ML-22261</i> 004470000001 | 430473031500 |
| NBU STATE 2-36G | 004471000001 | 430473051500 |
| NDC 69-29 ORI | <i>U-24230</i> 010915000001 | 430473158000 |
| NDK STORAGE | 024739000001 | |
| NDU 1-28 | <i>U-0576</i> 004581000001 | 430473126900 |
| OSCU II 1-34 | <i>U-49523</i> 019777000001 | 430473203900 |
| OSCU II 2-27 (DEV) | <i>U-49518</i> 001727000001 | 430473189800 |
| OSCU II FED #1 | <i>U-49518</i> 011041000001 | 430473172200 |
| STG 1-32 | <i>ML-3085</i> 005915000001 | 430471507100 |
| STG 2-28 | <i>U-0803</i> 005928000001 | 430471507200 |
| STG 6-20 | <i>Indian</i> 005936000001 | 430471507500 |
| STG 11-22 | <i>U-025960</i> 005919000001 | 430472019300 |
| STG 14-34 | <i>U-9613</i> 005922000001 | 430473059400 |
| STG 15-27 | <i>U-0803</i> 005923000001 | 430473060400 |
| STG 18-17 | <i>fee</i> 005926000001 | 430473061100 |
| STG 19-33 | <i>U-9613</i> 005927000001 | 430473065700 |
| STG 21-08 | <i>U-0283</i> 005930000001 | 430473065900 |
| STG 22-17 | <i>Indian</i> 005931000001 | 430473129900 |
| STG 33-17N | <i>Indian</i> 024128000001 | 430473244100 |
| STG 41-20 | <i>U-019362A</i> 021175000001 | 430473228000 |
| STG 44-8N | <i>U-0283</i> 025122000001 | 430473252000 |
| STG 48-17F | <i>Indian</i> 031389000001 | 430473272800 |
| STG 50-20F | <i>U-019362</i> 031390000001 | 430473310400 |
| STG 51-20F | <i>Indian</i> 031391000001 | 430473312000 |
| STG 52-08N | <i>U-0283</i> 031745000001 | 430473283400 |

EOG RESOURCES, INC.
UTAH OPERATED WELLS

| WELL NAME | | EOG PROPERTY # | API # |
|---------------------|---------|----------------|--------------|
| STG 53-08N | U-0283 | 032264000001 | 430473268200 |
| STG 56-20F | Indian | 032265000001 | 430473337000 |
| STG 57-08N | U-0283 | 032266000001 | 430473337100 |
| WILD HORSE FED 2-26 | U-3405 | 008266000001 | 430473188200 |
| WILD HORSE FED 2-35 | U-3405 | 019139000001 | 430473190100 |
| WILD HORSE FED 3-26 | U-43156 | 021869000001 | 430473237700 |
| WILD HORSE FED 3-35 | U-3405 | 021871000001 | 430473238900 |

OPERATOR CHANGE WORKSHEET

Attach all documentation received by the Division regarding this change.

Initial each listed item when completed. Write N/A if item is not applicable.

☐ Change of Operator (Well Sold)☐ Designation of Agent☐ Designation of Operator☒ Operator Name Change Only (MERGER)**ROUTING:**

| | |
|-------|---|
| 1-KDR | 6-KAS <input checked="" type="checkbox"/> |
| 2-GLH | 7-SJ |
| 3-JRB | 8-FILE |
| 4-CDW | |
| 5-KDR | |

The operator of the well(s) listed below has changed, effective: 8-30-99

TO:(New Operator) EOG RESOURCES INC.
 Address: P.O. BOX 4362
HOUSTON, TX 77210-4362
DEBBIE HAMRE
 Phone: (713)651-6714
 Account No. N9550

FROM:(Old Operator) ENRON OIL & GAS COMPANY
 Address: P.O. BOX 4362
HOUSTON, TX 77210-4362
DEBBIE HAMRE
 Phone: (713)651-6714
 Account No. N0401

ALL(S): Attach additional page(s) if needed.

| | | | |
|-------------------------------|--------------------------|---------------------------------------|--------------|
| Name: **SEE ATTACHED** | API: <u>43-047-32375</u> | Entity: <u>04905 S 14 T 9 S R 224</u> | Lease: _____ |
| Name: _____ | API: _____ | Entity: <u>S T R</u> | Lease: _____ |
| Name: _____ | API: _____ | Entity: <u>S T R</u> | Lease: _____ |
| Name: _____ | API: _____ | Entity: <u>S T R</u> | Lease: _____ |
| Name: _____ | API: _____ | Entity: <u>S T R</u> | Lease: _____ |
| Name: _____ | API: _____ | Entity: <u>S T R</u> | Lease: _____ |

OPERATOR CHANGE DOCUMENTATION

- VDR 1. (R649-8-10) Sundry or other legal documentation has been received from the **FORMER** operator (attach to this form) on 10.7.99.
- VDR 2. (R649-8-10) Sundry or other legal documentation has been received from the **NEW** operator on 10.7.99.
- VDR 3. The new company has been looked up in the **Department of Commerce, Division of Corporations Database** if the new operator above is not currently operating any wells in Utah. Is the operator registered with the State? Yes/No If yes, the company file number is _____. If no, Division letter was mailed to the new operator on _____.
- VDR 4. **Federal and Indian Lease Wells.** The BLM and/or the BIA has approved the operator change for all wells listed above involving Federal and/or Indian leases. BIM-Rec'd 10.20.99
BIA-Rec'd 3.10.99
- N/A 5. **Federal and Indian Units.** The BLM and/or the BIA has approved the operator change for the _____ unit and all wells listed above involving unit operations. (Name change only - BIM approved)
- N/A 6. **Federal and Indian Communitization Agreements ("CA").** The BLM and/or the BIA has approved the operator change for CA (Federal, Indian), CA No. _____, and all wells listed above involved in the CA.

* For wells located on a CA (state or fee) send a copy of the sundry notice of all wells involved to Teresa Thompson at the S.L. Office before approval.

7. **Underground Injection Control ("UIC") Program.** The Division has approved UIC Form 5, Transfer of Authority to Inject, for the enhanced/secondary recovery unit/project and/or for the water disposal well(s) listed above. ** need 1 for 43.*
- VDR 8. Changes have been entered in the **Oil and Gas Information System** for each well listed on 1.31.2000 ^{3.16.00} *Chy DTS*
9. Changes have been entered in **RBDMS** for each water/gas injection, water disposal well listed on _____.
10. Changes have been included on the monthly "Operator, Address, and Account Changes" memo on _____.
- VDR 11. An **Operator Change File** has been set up, and a copy of this page has been placed there for reference during routing and processing of the original documents.

ENTITY REVIEW

- VDR 1. (R649-8-7) Entity assignments have been reviewed for all wells listed above. Were entity changes made? Yes/No No If entity assignments were changed, attach copies of Form 6, Entity Action Form.
- VDR 2. Tax Commission, Trust Lands, and Forestry, Fire & State Lands have been **notified** through normal procedures of entity changes.

BOND VERIFICATION - (FEE LEASE WELLS)

- VDR 1. (R649-3-1) The **NEW** operator of any fee lease well(s) listed above has furnished a proper bond. *Rider # JT-1230 eff 10.4.99 St. Paul Fire & Marine (80,000)*
2. A copy of this form has been placed in the new and former operator's bond files on _____.
- VDR 3. The **FORMER** operator has requested a release of liability from their bond as of today's date No, Rider. If yes, Division response was made to this request by letter dated _____ (see bond file).

LEASE INTEREST OWNER NOTIFICATION OF RESPONSIBILITY

- VDR 1. E-mail sent on _____ to _____ at SITLA for changes involving State leases. (Wait two weeks before changing, unless the Division hears otherwise.) *(80,000 Statewide) St. Paul Fire & Marine*
- VDR 2. (R649-2-10) The **Former** operator of any Fee lease wells listed above has been contacted and informed by letter dated 2.1.2000, of their responsibility to notify all interest owners of this change. *JP-D921*

FILMING

1. All attachments to this form have been **microfilmed** on 3-26-01.

FILING

1. Copies of all attachments pertaining to each individual well have been filed in each well file.
2. The **original of this form**, and the **original attachments** have been filed in the Operator file(s).

COMMENTS